









MECHANICAL SYMBOLS LIST

<div>AC-1EF-1</div>		EQUIPMENT SYMBOL	MECHANICAL ABBREVIATIONS	
AIR DEVICES			AC	AIR CONDITIONING UNIT
<div><div>☒☒</div></div>	CEILING DIFFUSER SUPPLY		ACCU	AIR COOLED CONDENSING UNIT
<div><div>☐☐</div></div>	CEILING DIFFUSER RETURN		AFF	ABOVE FINISHED FLOOR
DUCT ACCESSORIES			AL	ACOUSTIC LINING
			CFM	CUBIC FEET OF AIR PER MINUTE
			CD	CONDENSATE DRAIN PIPE
			DN	DOWN
			FC	FLEXIBLE CONNECTION
			VD	VOLUME DAMPER
			<div></div>	VOLUME DAMPER W/ ACCESS DOOR
HVAC PIPING			CDS	CEILING DIFFUSER SUPPLY
<div>— CP —</div>	NEW CONDENSATE PIPING		CDR	CEILING DIFFUSER RETURN
CONTROLS AND SENSORS			OAI	OUTSIDE AIR INTAKE RISER
			OA	OUTSIDE AIR CFM
			REF	REFRIGERANT PIPING
<div>Ⓣ</div>	THERMOSTAT			

⑤	TEMPERATURE SENSOR
⑥	MANUAL ON/OFF SWITCH
⑦	SMOKE DETECTOR

DUCTWORK	
----------	--

	AIR DUCT W/ 1.5" ACOUSTICAL LINING
	FLEXIBLE DUCT
	FLEXIBLE CONNECTION
	RECTANGULAR DUCT (WIDTH X DEPTH)
	ROUND DUCT (DIAMETER)
	ROUND DUCT CROSS SECTION
	SUPPLY AIR RECTANGULAR DUCT CROSS SECTION
	RETURN AIR RECTANGULAR DUCT CROSS SECTION

MECHANICAL DRAWING LIST

M001.00	TITLE SHEET, SYMBOLS, ABBREVIATIONS AND NOTES
M002.00	MECHANICAL SPECIFICATION (1 OF 2)
M003.00	MECHANICAL SPECIFICATION (2 OF 2)
M100.00	MECHANICAL FLOOR PLAN AND SCHEDULE
M500.00	MECHANICAL DETAILS (1 OF 3)
M501.00	MECHANICAL DETAILS (2 OF 3)
M502.00	MECHANICAL DETAILS (3 OF 3)

NEW YORK BUILDING DEPARTMENT NOTES

ALL WORK SHALL COMPLY WITH APPLICABLE SECTIONS OF THE CITY OF NEW YORK BUILDING CODE, EFFECTIVE JULY 1, 2014 AND ALL AMENDMENTS AND RULES AND REGULATIONS OF THE DEPARTMENT OF BUILDINGS TO DATE.

1. THE CONTRACTOR SHALL ENGAGE THE SERVICES OF A PROFESSIONAL ENGINEER TO PROVIDE THE REQUIRED SPECIAL INSPECTIONS AND TESTS.

3. THE CONTRACTOR SHALL ENGAGE THE SERVICES OF A PROFESSIONAL ENGINEER TO PROVIDE THE REQUIRED SPECIAL INSPECTIONS AND TESTS.
2. TESTS WILL BE CONDUCTED UNDER DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, ARCHITECT OR OTHER PERSON HAVING NOT LESS THAN FIVE (5) YEARS EXPERIENCE SUPERVISING THE INSTALLATION OF SUCH MECHANICAL SYSTEMS. THE TESTS WILL SHOW COMPLIANCE WITH 2014 NEW YORK CITY BUILDING CODE .
3. THE LICENSED PROFESSIONAL ENGINEER, ARCHITECT OR OTHER PERSON HAVING NOT LESS THAN FIVE (5) YEARS EXPERIENCE SUPERVISING THE INSTALLATION OF SUCH MECHANICAL SYSTEMS AND CONDUCTING SUCH TESTS WILL FILE DOCUMENTATION AND REPORTS OF TESTS THAT THE SYSTEM COMPLIES WITH THE CONSTRUCTION DOCUMENTS AND APPLICABLE LAWS.
4. TESTS OF MECHANICAL SYSTEMS SHALL BE PERFORMED IN ACCORDANCE WITH SECTION MC 107 AND THE FOLLOWING SECTIONS OF THE 2014 NEW YORK CITY MECHANICAL CODE: :
 - A. VENTILATION SYSTEM SERVING COMMERCIAL COOKING APPLIANCES – MC 507.16
 - B. REFRIGERATION SYSTEMS – MC 1108
5. THE FOLLOWING WORK ITEMS, COMPONENTS, MATERIALS, CAPACITIES, ETC. SHALL COMPLY WITH THE REFERENCED CODE OR STANDARD:
 - A. STANDARDS OF HEATING – MC 309.1
 - B. DUCT CONSTRUCTION AND INSTALLATION– MC 603
 - C. AIR INTAKES, EXHAUSTS AND RELIEFS – IMC 401.5
 - D. AIR FILTERS – MC 605
6. MINIMUM TEMPERATURE TO BE MAINTAINED IN OCCUPIED SPACES DURING HEATING SEASON: 68 DEG. FAHRENHEIT.
7. VENTILATION FOR ALL AREA SHALL COMPLY WITH MC 401, 403.2.
8. A STATEMENT SHALL BE FILED BY THE OWNER OR TENANT IN POSSESSION THAT THE VENTILATION SYSTEM WILL BE KEPT IN CONTINUOUS OPERATION AT ALL TIMES DURING THE NORMAL OCCUPANCY OF THE STRUCTURE AS REQUIRED BY MC 403.3
9. REFER TO ARCHITECTURAL DRAWINGS FOR REQUIRED FIRE-RATED WALL AND SMOKE WALL CONSTRUCTION AND LOCATION.
10. THESE PLANS ARE APPROVED ONLY FOR THE WORK INDICATED ON THE APPLICATION SPECIFICATION SHEET. ALL OTHER MATTERS SHOWN ARE NOT TO BE RELIED UPON OR TO BE CONSIDERED AS EITHER BEING APPROVED OR IN ACCORDANCE WITH APPLICABLE CODES.
11. MECHANICAL SYSTEMS SHALL BE COMMISSIONED PER 2020-NYC ECC C403.2.2, C408.2.1, C408.2.5 FINAL COMMISSIONING REPORT SHALL BE DUE WITHIN 90 DAYS OF RECEIPT OF CERTIFICATE OF OCCUPANCY.
12. A COMMISSIONING PLAN SHALL BE DEVELOPED BY A LICENSED DESIGN PROFESSIONAL, MECHANICAL ENGINEER OR APPROVED AGENCY.
13. A PRELIMINARY REPORT OF COMMISSIONING TEST PROCEDURES AND RESULTS SHALL BE COMPLETED AND CERTIFIED BY THE LICENSED DESIGN PROFESSIONAL, ELECTRICAL ENGINEER, MECHANICAL ENGINEER OR APPROVED AGENCY AND PROVIDED TO THE BUILDING OWNER OR OWNER'S AUTHORIZED AGENT AS PER 2020-NYC ECC 2012 C408.2.4.
14. A WRITTEN REPORT DESCRIBING THE ACTIVITIES AND MEASUREMENTS COMPLETED IN ACCORDANCE WITH SECTION 2020-NYC ECC, C408.2.4.
15. ALL HEATING AND COOLING LOADS CALCULATED PER ASHRAE/ACCA 183.
16. SMOKE DETECTOR SHALL MEET UL268A.
17. INDOOR DUCT AND PLENUM INSULATION SCHEDULE:
 - A. CONCEALED, RECTANGULAR, ROUND AND FLAT-OVAL, SUPPLY-RETURN, OUTDOOR-AND EXHAUST-AIR DUCT AND AIR PLENUM INSULATION:
 - B. FLEXIBLE ELASTOMERIC, MINERAL-FIBER BLANKET, MINERAL-FIBER BOARD OR POLYOLEFIN WITH MINIMUM INSTALLED THERMAL RESISTANCE AS FOLLOWS:
UNCONDITIONED SPACES WITHIN BUILDING: R-6
WITHIN BUILDING ENVELOPE ASSEMBLY: R-8
OUTSIDE OF BUILDING: R-8

SCOPE OF WORK

SCOPE OF WORK

1. THE WORK UNDER CONTRACT INCLUDES ALL LABOR, MATERIALS AND APPLIANCES NECESSARY FOR THE FURNISHING, INSTALLING AND TESTING, COMPLETE AND READY FOR SAFE OPERATION OF THE SYSTEMS AS DESCRIBED IN THE SPECIFICATIONS, FLOOR PLAN(S) DESIGN, DETAIL DRAWINGS, NOTES, RFI'S, ETC. FOR THIS PROJECT. WORK SHALL BE INSTALLED IN A NEAT, WORKMANLIKE MANNER.
2. THE CONTRACTOR SHALL GIVE NECESSARY NOTICE, FILE DRAWINGS AND SPECIFICATIONS WITH THE DEPARTMENT HAVING JURISDICTION, OBTAIN PERMITS OR LICENSES NECESSARY TO CARRY OUT THIS WORK AND PAY ALL FEES THEREFOR. THE CONTRACTOR SHALL ARRANGE FOR INSPECTION AND TESTING OF ANY OR ALL PARTS OF THE WORK IF SO REQUIRED BY AUTHORITIES AND PAY ALL CHARGES FOR SAME. THE CONTRACTOR SHALL PAY ALL COSTS FOR, AND FURNISH TO THE OWNER BEFORE FINAL BILLING, ALL CERTIFICATES NECESSARY AS EVIDENCE THAT THE WORK INSTALLED CONFORMS WITH ALL REGULATIONS WHERE THEY APPLY TO THIS WORK.
3. THE CONTRACTOR SHALL FURNISH A WRITTEN GUARANTEE TO REPLACE OR REPAIR PROMPTLY AND ASSUME RESPONSIBILITY FOR ALL EXPENSES INCURRED FOR ANY WORKMANSHIP AND EQUIPMENT IN WHICH DEFECTS DEVELOP WITHIN ONE YEAR FROM THE DATE OF FINAL CERTIFICATE FOR PAYMENT AND/OR FROM DATE OR ACTUAL USE OF EQUIPMENT OR OCCUPANCY OF THE SPACES, BY OWNER, INCLUDED UNDER THE VARIOUS PARTS OF THIS WORK, WHICHEVER DATE OR OCCURRENCE IS LATER. THE GUARANTEE SHALL BE AS DIRECTED BY THE OWNER. THE GUARANTEE SHALL ALSO PROVIDE THAT WHERE DEFECTS OCCUR, THE CONTRACTOR WILL ASSUME RESPONSIBILITY FOR ALL EXPENSES INCURRED IN REPAIRING AND REPLACING WORK OF OTHER TRADES AFFECTED BY DEFECTS, REPAIRS OR REPLACEMENTS IN EQUIPMENT SUPPLIED BY THE CONTRACTOR.

TR8 ENERGY CODE PROGRESS INSPECTIONS (MECHANICAL)						
YES	NO	TAG	INSPECTION/TEST	FREQUENCY/MINIMUM	REFERENCE STANDARD (SEE ECC CHAPTER 6) OR OTHER CRITERIA	ECC OR OTHER CITATION

YES	NO	TAG	INSPECTION / TEST	FREQUENCY / MINIMUM	REFERENCE STANDARD (SEE ECC CHAPTER 6) OR OTHER CRITERIA	ECC OR OTHER CITATION
		IIB	MECHANICAL AND SERVICE WATER HEATING INSPECTIONS			
	X	IIB1	FIREPLACES: PROVISION OF COMBUSTION AIR AND TIGHT-FITTING FIREPLACE DOORS MUST BE VERIFIED BY VISUAL INSPECTION.	PRIOR TO FINAL CONSTRUCTION INSPECTION	APPROVED CONSTRUCTION DOCUMENTS; UL 127	C402.2.8; BC 2111; MC CHAPTERS 7, 8, 9; FGC CHAPTER 6
	X	IIB2	SHUTOFF DAMPERS: DAMPERS FOR STAIR AND ELEVATOR SHAFT VENTS AND OTHER OUTDOOR AIR INTAKES AND EXHAUST OPENINGS INTEGRAL TO THE BUILDING ENVELOPE MUST BE VISUALLY INSPECTED TO VERIFY THAT SUCH DAMPERS, EXCEPT WHERE PERMITTED TO BE GRAVITY DAMPERS, COMPLY WITH APPROVED CONSTRUCTION DRAWINGS. MANUFACTURER'S LITERATURE MUST BE REVIEWED TO VERIFY THAT THE PRODUCT HAS BEEN TESTED AND FOUND TO MEET THE STANDARD.	AS REQUIRED DURING INSTALLATION	APPROVED CONSTRUCTION DOCUMENTS; AMCA 500D	C402.5.5, C403.7.7; ASHRAE 90.1 – 6.4.3.4
	X	IIB3	HVAC-R EQUIPMENT: EQUIPMENT SIZING, EFFICIENCIES AND OTHER PERFORMANCE FACTORS OF ALL MAJOR EQUIPMENT UNITS, AS DETERMINED BY THE APPLICANT OF RECORD, AND NO LESS THAN 15% OF MINOR EQUIPMENT UNITS, SHALL BE VERIFIED BY VISUAL INSPECTION AND, WHERE NECESSARY, REVIEW OF MANUFACTURER'S DATA. POOL HEATERS AND COVERS SHALL BE VERIFIED BY VISUAL INSPECTION.	PRIOR TO FINAL PLUMBING AND CONSTRUCTION INSPECTION	APPROVED CONSTRUCTION DOCUMENTS	C403.1, C403.2, C403.3, C403.7.5, C404.9, C404.10, C406; ASHRAE 90.1 – 6.3, 6.4, 6.5, 6.7, 7.4, 7.5, 7.8, 10.4.6, APPENDIX I
	X	IIB4	HVAC-R SYSTEM CONTROLS: NO LESS THAN 20% OF EACH TYPE OF REQUIRED CONTROLS MUST BE VERIFIED BY VISUAL INSPECTION AND TESTED FOR FUNCTIONALITY AND PROPER OPERATION. SUCH CONTROLS MUST INCLUDE, BUT ARE NOT LIMITED TO: <ul style="list-style-type: none"> • THERMOSTATIC • OFF-HOUR • ZONES • FREEZE PROTECTION/SNOW- AND ICE-MELT SYSTEM • VENTILATION SYSTEM AND FAN CONTROLS • ENERGY RECOVERY SYSTEMS • KITCHEN/LAB EXHAUST SYSTEMS • FAN SYSTEMS SERVING SINGLE AND MULTIPLE ZONES • OUTDOOR HEATING SYSTEMS • HVAC CONTROL IN HOTEL/MOTEL GUEST ROOMS • AIR/WATER ECONOMIZERS & CONTROLS • HYDRONIC SYSTEMS • HEAT REJECTION SYSTEMS • HOT GAS BYPASS LIMITATION • REFRIGERATION SYSTEMS • DOOR SWITCHES • COMPUTER ROOM SYSTEMS • SERVICE WATER HEATING SYSTEMS • POOL HEATER AND TIME SWITCHES CONTROLS WITH SEASONALLY DEPENDENT FUNCTIONALITY: CONTROLS WHOSE COMPLETE OPERATION CANNOT BE DEMONSTRATED DUE TO PREVAILING WEATHER CONDITIONS TYPICAL OF THE SEASON DURING WHICH PROGRESS INSPECTIONS WILL BE PERFORMED SHALL BE PERMITTED TO BE SIGNED OFF FOR THE PURPOSE OF A TEMPORARY	AFTER INSTALLATION AND PRIOR TO FINAL ELECTRICAL AND CONSTRUCTION INSPECTION, EXCEPT THAT FOR CONTROLS WITH SEASONALLY DEPENDENT FUNCTIONALITY, SUCH TESTING MUST BE PERFORMED BEFORE SIGNOFF FOR ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY	APPROVED CONSTRUCTION DOCUMENTS, INCLUDING CONTROL SYSTEM NARRATIVES; ASHRAE GUIDELINE 1: THE HVAC COMMISSIONING PROCESS WHERE APPLICABLE	C403, C404, C406, ASHRAE 90.1 – 6.3, 6.4, 6.5, 6.6, 7.4, 7.5, APPENDIX I
	X	IIB5	HVAC-R DESIGN AND INSULATION: INSTALLED PIPING INSULATION MUST BE VISUALLY INSPECTED TO VERIFY PROPER INSULATION PLACEMENT AND VALUES. SERVICE HOT WATER DISTRIBUTION SYSTEMS MUST BE INSPECTED TO VERIFY THE SUPPLY OF HEATED WATER.	AFTER INSTALLATION AND PRIOR TO CLOSING SHAFTS, CEILINGS AND WALLS	APPROVED CONSTRUCTION DOCUMENTS; SMACNA DUCT CONSTRUCTION STANDARDS, METAL AND FLEXIBLE	C403.11, C404.4, C404.5; MC 603.9; ASHRAE 90.1 – 6.3, 6.4.4, 6.8.2, 6.8.3; 7.4.3
	X	IIB6	DUCT LEAKAGE TESTING, INSULATION AND DESIGN: FOR DUCT SYSTEMS DESIGNED TO OPERATE AT STATIC PRESSURES IN EXCESS OF 3 INCHES W.G. (747 PA), REPRESENTATIVE SECTIONS, AS DETERMINED BY THE PROGRESS INSPECTOR, TOTALING AT LEAST 25% OF THE DUCT AREA, MUST BE TESTED TO VERIFY THAT ACTUAL AIR LEAKAGE IS BELOW ALLOWABLE AMOUNTS. INSTALLED DUCT INSULATION MUST BE VISUALLY INSPECTED TO VERIFY PROPER INSULATION PLACEMENT AND VALUES. JOINTS, LONGITUDINAL AND TRANSVERSE SEAMS AND CONNECTIONS IN DUCTWORK MUST BE VISUALLY INSPECTED FOR PROPER SEALING.	AFTER INSTALLATION AND SEALING AND PRIOR TO CLOSING SHAFTS, CEILINGS AND WALLS	APPROVED CONSTRUCTION DOCUMENTS; SMACNA HVAC AIR DUCT LEAKAGE TEST MANUAL; SMACNA DUCT CONSTRUCTION STANDARDS, METAL AND FLEXIBLE	C403.11; ASHRAE 90.1 – 6.4.4.2.2

	IID	OTHER
--	-----	-------

X	IID1	<p>MAINTENANCE INFORMATION: MAINTENANCE MANUALS FOR MECHANICAL, SERVICE HOT WATER AND ELECTRICAL EQUIPMENT AND SYSTEMS REQUIRING PREVENTIVE MAINTENANCE MUST BE REVIEWED FOR APPLICABILITY TO INSTALLED EQUIPMENT AND SYSTEMS BEFORE SUCH MANUALS ARE PROVIDED TO THE OWNER. LABELS REQUIRED FOR SUCH EQUIPMENT OR SYSTEMS MUST BE INSPECTED FOR ACCURACY AND COMPLETENESS.</p>	<p>PRIOR TO SIGN-OFF OR ISSUANCE OF FINAL CERTIFICATE OF OCCUPANCY</p>	<p>APPROVED CONSTRUCTION DOCUMENTS, INCLUDING ELECTRICAL DRAWINGS WHERE APPLICABLE; ASHRAE GUIDELINE 4: PREPARATION OF OPERATING AND MAINTENANCE DOCUMENTATION FOR BUILDING SYSTEMS</p>	<p>C408.11, C408.2.5.2, C408.3.2; ASHRAE 90.1 – 4.2.2.3, 6.7.2.2, 6.7.2.3.5.2, 8.7.2, 9.4.3.2.2, 9.7.2.2</p>
---	------	--	--	---	--

		TR1 Special Inspections (MECHANICAL)	
YES	NO	INSPECTION	NYC BC 2014
X		MECHANICAL SYSTEMS	BC 1704.16
X		FIRE RESISTANT PENETRATION AND JOINTS	BC 1704.27
X		POST INSTALLED ANCHORS	BC 1704.32

Cha Cha
MATCHA

CHA CHA MATCHA
EMPIRE STORES

REVISIONS

[illegible]

PROJECT NUMBER: 22-097

TITLE SHEET,
SYMBOLS,
ABBREVIATIONS
AND NOTES

M001.00

GENERAL NOTES

1. CONTRACTOR SHALL SURVEY THE AREA OF THIS WORK BEFORE SUBMITTING A BID AND SHALL BE RESPONSIBLE FOR NOTIFYING THE ARCHITECT OF ANY CONDITIONS WHICH WOULD PREVENT THE INSTALLATION OF THE WORK AS SHOWN ON DRAWINGS.
2. ALL APPLICABLE CODES, LAWS AND REGULATIONS GOVERNING OR RELATING TO ANY PORTION OF THIS WORK ARE HEREBY INCORPORATED INTO AND MADE A PART OF THESE SPECIFICATIONS, AND THEIR PROVISIONS SHALL BE CARRIED OUT BY THE CONTRACTOR WHO SHALL INFORM THE OWNER, PRIOR TO SUBMITTING A PROPOSAL, OF ANY WORK OR MATERIALS WHICH VIOLATE ANY OF THE ABOVE LAWS AND REGULATIONS. ANY WORK DONE BY THE CONTRACTOR CAUSING SUCH VIOLATION SHALL BE CORRECTED BY THE CONTRACTOR.
3. BEFORE PROCEEDING WITH ANY WORK IN OCCUPIED OR USED AREAS, THE CONTRACTOR SHALL APPLY TO OWNER FOR PERMISSION TO ENTER SUCH AREAS. THE CONTRACTOR IS OBLIGED TO PERFORM HIS WORK ONLY AT THE TIMES DESIGNATED BY OWNER. THERE WILL BE NO ADDITIONAL COMPENSATION FOR THE WORK PERFORMED AFTER HOURS OR ON OFF-DAYS WITHOUT PRIOR WRITTEN APPROVAL.
4. THE WORK IN THE BUILDING SHALL BE DONE WHEN AND AS DIRECTED, AND IN A MANNER SATISFACTORY TO THE OWNER. THE WORK SHALL BE PERFORMED SO AS TO CAUSE THE LEAST POSSIBLE INCONVENIENCE AND DISTURBANCE TO THE PRESENT OCCUPANTS.
5. THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE PREDICATED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS. WHEN SO DIRECTED, HOWEVER, THE CONTRACTOR SHALL INSTALL WORK IN OVERTIME AND THE PROPORTIONAL COST TO CHARGE THEREFOR SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.
6. CONTRACTOR SHALL ASCERTAIN THE APPROPRIATE METHOD FOR BRINGING THE UNITS INTO AND THROUGH THE BUILDING TO POSITION UNIT IN LOCATION SHOWN ON THE PLANS, WHERE NECESSARY. EQUIPMENT SHALL BE SHIPPED FROM MANUFACTURER IN SECTIONS OF SIZE SUITABLE FOR MOVING THROUGH RESTRICTIVE SPACES. COORDINATE WITH BUILDING OWNER APPROPRIATE TIMES OF DAY SUCH EQUIPMENT MAY BE MOVED THROUGH ALL AREAS.
7. DUCTWORK AND PIPING IS SHOWN DIAGRAMMATICALLY AND DOES NOT SHOW ALL OFFSETS, DROPS AND RISERS OF RUNS. THE CONTRACTOR SHALL MAKE ALLOWANCE FOR SUCH OFFSETS FOR ROUTING OF DUCTWORK AND PIPING TO AVOID OBSTRUCTIONS. EXACT LOCATIONS ARE SUBJECT TO APPROVAL OF ARCHITECT. COORDINATION WITH THE OTHER TRADES IS REQUIRED.
8. SUPPORT ALL DUCTWORK AND PIPING FROM BUILDING STRUCTURE AND/OR FRAMING IN AN APPROVED MANNER. WHERE OVERHEAD CONSTRUCTION DOES NOT PERMIT FASTENING OR SUPPORTS FOR EQUIPMENT, FURNISH ADDITIONAL FRAMING. INSERTS SHALL BE STEEL, SLOTTED TYPE, AND FACTORY PAINTED. SINGLE ROD SHALL BE SIMILAR TO GRINNELL FIG. 281. MULTI-ROD SHALL BE SIMILAR TO FEE & MASON SERIES 9000 WITH END CAPS AND CLOSURE STRIPS. MAXIMUM LOADING INCLUDING PIPES, DUCTWORK, CONTENTS, AND EQUIPMENT SHALL NOT EXCEED 75% OF RATED INSERT CAPABILITY. WHEN SUPPORTING FROM BUILDING USE BEAM CLAMPS IN APPROVED MANNER.
9. PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE WATERPROOFING INTEGRITY OF THIS BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF PIPES, DUCTWORK, COVERS, AND EQUIPMENT. PROVIDE EQUIPMENT CURBS AND DUNNAGE STEEL AS REQUIRED.
10. SEAL OPENINGS AROUND DUCTS AND PIPING THROUGH PARTITIONS, WALLS AND FLOORS (NOT IN SHAFTS) WITH MINERAL WOOL OR OTHER NONCOMBUSTIBLE MATERIAL. (FIBERGLASS INSULATION IS NOT ACCEPTABLE).
11. WHERE PENETRATIONS THROUGH FIRE RATED WALLS ARE NOT FIRE PROOFED THIS CONTRACTOR SHALL BE RESPONSIBLE TO SEAL SAME TO MAINTAIN THE RATED INTEGRITY.
12. INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATION, MAINTENANCE AND REPAIR. MINOR DEVIATIONS FROM DRAWINGS MAY BE MADE TO ACCOMPLISH THIS, BUT CHANGES WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.
13. ACCESS DOORS ARE REQUIRED FOR ALL BUILDING SERVICE VALVES THAT RUN THROUGH THE SPACE, AND ACCESS DOOR SHALL HAVE THE EQUAL RATED CAPACITY (1HR, 2HR, ETC.) AS WALL. COORDINATE ALL LOCATIONS OF ACCESS DOORS WITH THE ARCHITECT.
14. REMOVABLE ACCESS TILE AND/OR ACCESS DOOR ARE REQUIRED IN HUNG CEILINGS, SHAFTS AND WALLS FOR ALL VOLUME AND FIRE DAMPERS, AUTOMATIC DAMPERS AND ALL OTHER MECHANICAL EQUIPMENT AND DEVICES. HVAC CONTRACTOR TO FURNISH EXCESS LOCATION REQUIREMENTS TO GENERAL CONTRACTOR. ACCESS TILE IDENTIFICATION: PROVIDE BUTTONS, TABS, AND MARKERS TO IDENTIFY LOCATION OF CONCEALED VALVES, DAMPERS AND EQUIPMENT.
15. THE CONTRACTOR SHALL KEEP ALL EQUIPMENT AND MATERIALS, AND ALL PARTS OF THE BUILDING, EXTERIOR SPACES AND ADJACENT STREETS, SIDEWALKS AND PAVEMENTS, FREE FROM MATERIAL AND DEBRIS RESULTING FROM THE EXECUTION OF THIS WORK. EXCESS MATERIALS WILL NOT BE PERMITTED TO ACCUMULATE EITHER ON THE INTERIOR OR THE EXTERIOR.
16. MATERIALS AND WORKMANSHIP, UNLESS OTHERWISE NOTED, SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.
17. ALL EQUIPMENT SHALL BE PROVIDED WITH ONE YEAR WARRANTY PARTS AND LABOR AND FIVE YEARS ON COMPRESSORS. WARRANTY PERIOD BEGINS UPON PROJECT ACCEPTANCE
18. ALL MATERIAL AND EQUIPMENT TO BE NEW UNLESS OTHERWISE NOTED AND SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.
19. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HIS WORK WITH ITS COMPLETION AND FINAL ACCEPTANCE AND SHALL REPLACE ANY OF THE SAME WHICH MAY BE DAMAGED, LOST, OR STOLEN WITHOUT ADDITIONAL COST TO THE OWNER.

20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE FAILURE OF ANY DUCTWORK SYSTEM OR EQUIPMENT TO FUNCTION PROPERLY UPON COMPLETION OF HIS WORK UPON SAID SYSTEM OR EQUIPMENT.
21. SUBMIT SHOP DRAWING OF ALL WORK WHICH MUST BE APPROVED BY THE ARCHITECT AND ENGINEER BEFORE WORK COMMENCES.
22. INSURANCE: IN ACCORDANCE WITH BUILDING REQUIREMENTS THE CONTRACTOR SHALL INCLUDE A HOLD HARMLESS CLAUSE FOR OWNER AND ENGINEER.
23. THE FINAL ACCEPTANCE WILL BE MADE AFTER THE CONTRACTOR HAS ADJUSTED HIS EQUIPMENT, BALANCED THE VARIOUS SYSTEMS, DEMONSTRATED THAT IT FULFILLS THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS AND HAS FURNISHED ALL THE REQUIRED CERTIFICATES OF INSPECTION AND APPROVAL.
24. SPECIFICATIONS ARE OF SIMPLIFIED FORM AND INCLUDE INCOMPLETE SENTENCES. WORDS OR PHRASES SUCH AS "THE CONTRACTOR SHALL," "SHALL BE," "FURNISH," "PROVIDE," "A," "THE," AND "ALL" HAVE BEEN OMITTED FOR BREVITY.
25. WHERE A CONFLICT EXISTS BETWEEN THE DRAWINGS, THE SPECIFICATIONS OR ANY OTHER CONSTRUCTION DOCUMENT, THE ONE WITH THE MOST STRINGENT REQUIREMENT(S) SHALL APPLY.

DEFINITIONS:

- 1) "PROVIDE": TO SUPPLY, INSTALL AND CONNECT UP COMPLETE AND READY FOR SAFE AND REGULAR OPERATION THE PARTICULAR WORK REFERRED TO UNLESS SPECIFICALLY OTHERWISE NOTED.
- 2) "INSTALL": TO ERECT, MOUNT AND CONNECT COMPLETE WITH RELATED ACCESSORIES.
- 3) "FURNISH" OR "SUPPLY": TO PURCHASE, PROCURE, ACQUIRE AND DELIVER COMPLETE WITH RELATED ACCESSORIES.

GENERAL HVAC NOTES

- PROVIDE ALL MATERIAL AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE MECHANICAL SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.
2. CONTRACT DOCUMENT DRAWINGS FOR MECHANICAL WORK (HVAC, PLUMBING, AND FIRE PROTECTION) ARE DIAGRAMMATIC AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY.
3. THE LOCATIONS OF ALL ITEMS SHOWN ON THE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT FIXED BY DIMENSIONS ARE APPROXIMATE ONLY. THE EXACT LOCATIONS ARE NECESSARY TO SECURE THE BEST CONDITIONS AND RESULTS MUST BE DETERMINED BY THE PROJECT SITE CONDITIONS AND SHALL HAVE THE APPROVAL OF THE ENGINEER BEFORE BEING INSTALLED. DO NOT SCALE DRAWINGS.
4. WHEN MECHANICAL WORK (HVAC, PLUMBING, SHEET METAL, FIRE PROTECTION, ETC.) IS SUBCONTRACTED, IT SHALL BE THE MECHANICAL CONTRACTOR'S RESPONSIBILITY TO COORDINATE SUBCONTRACTORS AND THE ASSOCIATED CONTRACTS. WHEN DISCREPANCIES ARISE PERTAINING TO WHICH CONTRACTOR PROVIDES A PARTICULAR ITEM OF THE MECHANICAL CONTRACT OR WHICH CONTRACTOR PROVIDES FINAL CONNECTIONS FOR A PARTICULAR ITEM OF THE MECHANICAL CONTRACT, IT SHALL BE BROUGHT TO THE ATTENTION OF THE MECHANICAL CONTRACTOR, WHOSE DECISION SHALL BE FINAL.
5. COORDINATE CONSTRUCTION OF ALL MECHANICAL WORK WITH ARCHITECTURAL, STRUCTURAL, CIVIL, ELECTRICAL WORK, ETC., SHOWN ON OTHER CONTRACT DOCUMENT DRAWINGS.
6. INSTALL ALL MECHANICAL EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS.
7. WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF EQUIPMENT ARE REQUIRED, THE PRODUCT OF ONE MANUFACTURER SHALL BE USED.
8. COORDINATE ALL EQUIPMENT CONNECTIONS WITH MANUFACTURERS' CERTIFIED DRAWINGS. COORDINATE AND PROVIDE ALL DUCT AND PIPING TRANSITIONS REQUIRED FOR FINAL EQUIPMENT CONNECTIONS TO FURNISHED EQUIPMENT. FIELD VERIFY AND COORDINATE ALL DUCT AND PIPING DIMENSIONS BEFORE FABRICATION.
9. ALL CONTROL WIRE AND CONDUIT SHALL COMPLY WITH THE NATIONAL ELECTRIC CODE AND ELECTRICAL DIVISION OF THE SPECIFICATION.
10. PROVIDE VIBRATION ISOLATION FOR ALL MECHANICAL EQUIPMENT TO PREVENT TRANSMISSION OF VIBRATION TO BUILDING STRUCTURE.
11. PROVIDE VIBRATION ISOLATORS FOR ALL PIPING SUPPORTS CONNECTED TO, AND WITHIN 50 FT. OF, ISOLATED EQUIPMENT (EXCEPT AT BASE ELBOW SUPPORTS AND ANCHOR POINTS).
12. LOCATE ALL TEMPERATURE, PRESSURE, AND FLOW MEASURING DEVICES IN ACCESSIBLE LOCATIONS WITH THE STRAIGHT SECTION OF PIPE OR DUCT UP- AND DOWNSTREAM AS RECOMMENDED BY THE MANUFACTURER FOR GOOD ACCURACY.
13. WHERE BEAMS ARE INDICATED TO BE PENETRATED WITH DUCTWORK OR PIPING, COORDINATE DUCTWORK AND PIPING LAYOUT WITH BEAM OPENING SIZE AND OPENING LOCATIONS. COORDINATION SHALL BE DONE PRIOR TO THE FABRICATION OF DUCTWORK, CUTTING OF PIPING, OR FABRICATION OF BEAMS.
14. ALL MISCELLANEOUS STEEL REQUIRED TO ENSURE PROPER INSTALLATION AND AS SHOWN IN THE DETAILS FOR PIPING, DUCTWORK, AND EQUIPMENT (UNLESS OTHERWISE NOTED) SHALL BE FURNISHED AND INSTALLED BY THE MECHANICAL CONTRACTOR.
15. PROVIDE ACCESS PANELS FOR INSTALLATION IN WALLS AND CEILINGS, WHERE REQUIRED, TO SERVICE DAMPERS, VALVES, SMOKE DETECTORS, AND OTHER CONCEALED MECHANICAL EQUIPMENT. ACCESS PANELS SHALL BE TURNED OVER TO THE GENERAL CONTRACTOR FOR INSTALLATION. ACCESS PANELS SHALL HAVE THE EQUAL RATED CAPACITY (1HR, 2HR, ETC.) AS WALL.
16. MECHANICAL EQUIPMENT, DUCTWORK, AND PIPING SHALL NOT BE SUPPORTED FROM A METAL DECK.

17. ALL EQUIPMENT, PIPING, DUCTWORK, ETC., SHALL BE SUPPORTED AS DETAILED, SPECIFIED AND REQUIRED TO PROVIDE A VIBRATION-FREE INSTALLATION.
18. ALL DUCTWORK, PIPING, AND EQUIPMENT SUPPORTED FROM STRUCTURAL STEEL SHALL BE COORDINATED WITH THE GENERAL CONTRACTOR. ALL ATTACHMENTS TO STEEL BAR JOISTS, TRUSSES, OR JOIST GIRDERS SHALL BE AT PANEL POINTS. PROVIDE BEAM CLAMPS MEETING MSS STANDARDS. WELDING TO STRUCTURAL MEMBERS SHALL NOT BE PERMITTED. THE USE OF C-CLAMPS SHALL NOT BE PERMITTED.
19. LOCATIONS AND SIZES OF ALL FLOOR, WALL, AND ROOF OPENINGS SHALL BE COORDINATED WITH ALL OTHER TRADES INVOLVED.
20. ALL OPENINGS IN FIRE WALLS DUE TO DUCTWORK, PIPING, CONDUIT, ETC., SHALL BE FIRE STOPPED WITH A PRODUCT SIMILAR TO 3M OR APPROVED EQUIVAL.
21. ALL AIR CONDITIONING CONDENSATE DRAIN LINES FROM EACH AIR HANDLING UNIT SHALL BE PIPED FULL SIZE OF THE UNIT DRAIN OUTLET, WITH "P" TRAP, AND PIPED TO THE NEAREST DRAIN. SEE THE DETAILS SHOWN IN THE DRAWINGS OR THE CONTRACT SPECIFICATIONS FOR THE DEPTH OF THE AIR CONDITIONING CONDENSATE TRAP.
22. REFER TO TYPICAL DETAILS FOR DUCTWORK, PIPING, AND EQUIPMENT INSTALLATION.
23. REINFORCEMENT, DETAILING, AND PLACEMENT OF CONCRETE SHALL CONFORM TO ASTM 315 AND ACI 318. CONCRETE SHALL CONFORM TO ASTM C94. CONCRETE WORK SHALL CONFORM TO ACI 318 PART ENTITLED "CONSTRUCTION REQUIREMENTS". COMPRESSIVE STRENGTH IN 28 DAYS SHALL BE 3,000 PSI. TOTAL AIR CONTENT OR EXTERIOR CONCRETE SHALL BE BETWEEN 5 AND 7 PERCENT BY VOLUME. SLUMP SHALL BE BETWEEN 8" AND 4 IN. CONCRETE SHALL BE CURED FOR 7 DAY AFTER PLACEMENT.
24. CONCRETE HOUSEKEEPING PADS TO SUIT MECHANICAL EQUIPMENT SHALL BE SIZED AND LOCATED BY THE MECHANICAL CONTRACTOR. MINIMUM CONCRETE PAD THICKNESS SHALL BE 6 IN. PAD SHALL EXTEND BEYOND THE EQUIPMENT A MINIMUM OF 6 IN. ON EACH SIDE. CONCRETE HOUSEKEEPING PADS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR. IT SHALL BE THE RESPONSIBILITY OF THE MECHANICAL CONTRACTOR TO COORDINATE THE SIZE AND LOCATION OF CONCRETE HOUSEKEEPING PADS WITH THE GENERAL CONTRACTOR.
25. ALL TESTS SHALL BE COMPLETED BEFORE ANY MECHANICAL EQUIPMENT OR PIPING INSULATION IS APPLIED.
26. TESTING, ADJUSTING, AND BALANCING AGENCY SHALL BE A MEMBER OF THE ASSOCIATED AIR BALANCE COUNCIL (AABC) OR THE NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB). TESTING, ADJUSTING, AND BALANCING SHALL BE PERFORMED IN ACCORDANCE WITH THE AABC STANDARDS.

AIR OUTLETS

GENERAL

- 1) MARGIN TYPES, COLORS, FINISH AND METHODS OF ATTACHMENT FOR ALL DIFFUSERS, GRILLES AND REGISTERS SHALL BE COORDINATED WITH ARCHITECTURAL CEILING AND WALL DETAILS AND SPECIFICATIONS.
- 2) FRAME TYPE SUITABLE FOR MOUNTING IN CEILING OR WALL CONSTRUCTION AS INDICATED ON ARCHITECTURAL PLANS.
- 3) EXACT LOCATION OF ALL AIR OUTLETS AS PER ARCHITECTURAL PLANS.
- 4) SUITABLE FOR OPERATION AT 20% EXCESS AND 20% LESS THAN NOTED CAPACITY FOR CONSTANT VOLUME SYSTEMS AND AT 20% EXCESS AND 80% LESS THAN NOTED CAPACITY FOR VARIABLE VOLUME SYSTEMS. MANUFACTURER RESPONSIBLE FOR EXAMINING APPLICATION OF EACH OUTLET AND GUARANTEE THAT EACH WILL PROVIDE REQUIRED NC LEVELS AND COMFORT SPACE CONDITIONS WITHOUT DRAFTS THROUGHOUT OPERATING RANGE.
- 5) ALL DIFFUSERS SHALL BE PROVIDED WITH OPPOSED BLADE VOLUME DAMPERS. DAMPER OPERATING LEVERS SHALL BE ACCESSIBLE AT THE FACE OF AIR OUTLETS.
 - A. SQUARE DIFFUSERS: DIFFUSERS SHALL BE STEEL CONSTRUCTION PAINTED WHITE SIMILAR TO ANEMOSTAT NOISE CONTROL.
 - B. PROVIDE SOUND LINING FOR THE FOLLOWING DUCTWORK:
 - 1) ALL DUCTWORK WITHIN NOT LESS THAN 20 FT ON EACH SIDE OF ALL FANS AND AC UNITS.
 - 2) AIR TRANSFER DUCTS.
 - 3) DOWNSTREAM OF ALL CONSTANT VOLUME BOXES FOR A MINIMUM OF 15 FT.
 - 4) ALL MIXED AIR PLENUMS.
 - 5) FULL EXTENT OF SUPPLY DUCTS SERVING CONFERENCE ROOMS.
 - 6) ALL EXPOSED INTERIOR SUPPLY DUCTWORK.
 - 7) ALSO WHERE NOTED ON A DRAWING.

C. SOUND LINING

- DENSITY, 1.5 IN. THICKNESS, MAXIMUM 0.25 K FACTOR AT 75 DEG C MEAN TEMPERATURE WITH ACRYLIC COATED FINISH FACTORY APPLIED EDGES COATING AND STENOLED IN ACCORDANCE WITH NFPA 90. FLAMESPREAD SHALL BE A MAXIMUM OF 25. LINING SHALL NOT SUPPORT MICROBIAL GROWTH AND SHALL BE TESTED IN ACCORDANCE WITH ASTM C 1071 AND ASTM G21/G22. SIMILAR TO MANVILLE PERMACOTE LINA SOUND.
- D. ALL SOUND LINING, ADHESIVES, FACES AND ACCESSORIES TO BE APPLIED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, EXCEPT AS OTHERWISE NOTED.

PIPING INSULATION

- A. PIPING SERVING AS PART OF A HEATING OR COOLING SYSTEM SHALL BE THERMALLY INSULATED IN ACCORDANCE WITH TABLE C403.11.3.
- B. PIPING, VALVES AND FITTINGS TO BE INSULATED:
- 1) LOW TEMPERATURE PIPING SYSTEMS - 0 TO 60 DEG F INCLUDING:
CONDENSATE DRAIN PIPING.

INSULATION SCHEDULE — PIPING				
SERVICE	SIZE	THICKNESS	MATERIAL	FINISH
REFRIGERANT PIPING		1.5"	P-6	
CONDENSER DRAIN PIPING IF RUNNING THROUGH (EXTERIOR WALL)		1.0"	P-6	

- PROTECTIVE COVERINGS SHALL BE INSTALLED ON AREAS OF INSULATION THAT ARE EXPOSED TO WEATHER OR SUBJECT TO MECHANICAL DAMAGE. THE PROTECTIVE COVERING SHALL BE:
- a. ARMA-CHEK SILVER[®] MULTI-LAYER LAMINATE OF ALUMINUM, COATED WITH A UV PROTECTIVE FILM AND BACKED WITH A FLEXIBLE PVC FILM. THE MATERIAL SHOULD BE ADHERED WITH ARMAFLEX 520 ADHESIVE OR EQUIVALENT, AND ALL JOINTS AND SEAMS SECURED WITH "ARMA-CHEK SILVER TAPE". INSTALLATION SHALL BE IN ALL CASES TO THE MANUFACTURER'S RECOMMENDATIONS.
- OR
- b. HIGH DENSITY RUBBER CLADDING OF THE "ARMA-CHECK R" TYPE BONDED USING AN APPROPRIATE FULL CONTACT ADHESIVE WITH A MINIMUM 1/8" MM OVERLAP AT ALL BUTT JOINTS. LONGITUDINAL SEAMS, A WEATHER-PROOF MASTIC SEALANT SHALL BE APPLIED OVER ALL SEAMS AND JOINTS. ALL MATERIAL SHALL BE OVERLAPPED AND STAGGERED IN SUCH A WAY AS TO ENSURE A WATERSHED IS ALWAYS PROVIDED. INSTALLATION SHALL BE IN ALL CASES TO THE MANUFACTURER'S RECOMMENDATIONS. ALL EXCESS ADHESIVE VISIBLE ON THE SURFACE OF THE COMPLETED ASSEMBLY SHALL BE REMOVED USING AN APPROPRIATE CLEANING MATERIAL.
- OR
- c. METAL CLADDING, COMPRISED OF COATED SHEET METAL, WITH ALL EXTERNAL JOINTS AND FIXING MADE WEATHER-PROOF WITH SILICONE SEALANT.
- MATERIAL:
- 1) TYPE P-1: MINIMUM 4 LB DENSITY MOLDED FIBERGLASS, MAXIMUM 0.24 K-FACTOR AT 75 DEG F MEAN TEMPERATURE WITH FACTORY-APPLIED FIRE-RETARDANT FOIL-SKRIM-KRAFT FACING. ALL SERVICE JACKET. SIMILAR TO OWENS-CORNING 650 ASJ.
- 2) TYPE P-3: MINIMUM 4 LB DENSITY MOLDED FIBERGLASS FITTING, MAXIMUM 0.23 K-FACTOR AT 75 DEG F MEAN TEMPERATURE SIMILAR TO EPOLUX HMFAB MOLDED FITTINGS.
- 3) TYPE P-4: MINIMUM 1 LB DENSITY FIBERGLASS FITTING INSERTS, MAXIMUM 0.27 K-FACTOR AT 75 DEG F MEAN TEMPERATURE SIMILAR TO MANVILLE HI-LO TEMP INSULATION INSERTS.
- 4) TYPE P-6: MINIMUM 6 LB MOLDED FOAMED PLASTIC. MAXIMUM 0.27 K-FACTOR AT 75 DEG F MEAN TEMPERATURE. MAXIMUM 0.17 PERMEANCE. SIMILAR TO ARMSTRONG ARMAFLEX II.
- FINISH:
- 1) TYPE F-1: FITTING COVER, MOLDED WHITE PVC JACKET, UL CLASS 1, MAXIMUM PERMEANCE 0.05 SIMILAR TO MANVILLE ZESTRON.
- 2) TYPE F-2: WHITE VAPOR BARRIER COATING WITH 10X10 OR 20X20 MESH WHITE GLASS, POLYESTER OR NYLON CLOTH REINFORCING MEMBRANE, MINIMUM 31 MIL DRY FILM THICKNESS. SIMILAR TO FOSTER TITE-FIT, UL LABEL.
- 3) TYPE F-4: ALUMINUM JACKETING WITH MINIMUM 0.016 IN. WALL THICKNESS AND LONGITUDINAL JOINTS WITH LOCK SEAMS.
- 4) TYPE F-6: WHITE FINISHING AND INSULATING CEMENT APPLIED OVER HEXAGONAL WIRE MESH. CEMENT SIMILAR TO KEENE SUPERSLICK.
- INSTALLATION:
- 1) BEFORE APPLYING INSULATION ALL PRESSURE AND LEAK TESTS SHALL BE COMPLETED AND APPROVED.
- 2) ALL INSULATION SHALL BE BUTTED FIRMLY TOGETHER. PROVIDE 2 IN. LAMP STRIPS AT ALL SEAMS SECURED WITH ADHESIVE. USE VAPOR BARRIER TAPE AND VAPORSEAL ADHESIVE WHERE REQUIRED. STAPLES NOT PERMITTED. REFRIGERANT PIPING INSULATION SHALL HAVE MITERED FITTINGS.
- 3) ALL INSULATION AND VAPOR BARRIERS SHALL BE CONTINUOUS PASSING THROUGH SLEEVES, HANGERS, ETC., OR OTHER OPENINGS. PROVIDE SADDLES OR SHIELDS FOR PROTECTION AT HANGING.
- 4) INSULATION FOR STRAINERS OR OTHER FITTINGS OR ACCESSORIES REQUIRING SERVICING OR INSPECTION SHALL HAVE INSULATION REMOVABLE AND REPLACEABLE WITHOUT DAMAGE.
- HERMISTATIC CONTROLS:
- a. GENERAL:
- THE SUPPLY OF HEATING AND COOLING ENERGY TO EACH ZONE SHALL BE INDIVIDUALLY CONTROLLED BY THERMOSTATIC CONTROLS RESPONDING TO TEMPERATURE WITHIN THE ZONE. FOR THE PURPOSES OF SECTION 6.4.3.1, A DWELLING UNIT SHALL BE PERMITTED TO BE CONSIDERED A SINGLE ZONE.
- b. DEAD BAND:
- WHERE USED TO CONTROL BOTH HEATING AND COOLING, THERMOSTATIC CONTROLS SHALL BE CAPABLE OF PROVIDING A TEMPERATURE RANGE OR DEAD BAND OF AT LEAST 5°F WITHIN WHICH THE SUPPLY OF HEATING AND COOLING ENERGY TO THE ZONE IS SHUT OFF OR REDUCED TO A MINIMUM.
- c. SETBACK CONTROLS:
- HEATING SYSTEMS LOCATED IN CLIMATE ZONES 2-8 SHALL BE EQUIPPED WITH CONTROLS THAT HAVE THE CAPABILITY TO AUTOMATICALLY RESTART AND TEMPORARILY OPERATE THE SYSTEM AS REQUIRED TO MAINTAIN ZONE TEMPERATURES ABOVE A HEATING SETPOINT ADJUSTABLE DOWN TO 55°F OR LOWER. COOLING SYSTEMS LOCATED IN CLIMATE ZONES 1B, 2B, AND 3B SHALL BE EQUIPPED WITH CONTROLS THAT HAVE THE CAPABILITY TO AUTOMATICALLY RESTART AND TEMPORARILY OPERATE THE SYSTEM AS REQUIRED TO MAINTAIN ZONE TEMPERATURES BELOW A COOLING SETPOINT ADJUSTABLE UP TO 90°F OR HIGHER OR TO PREVENT HIGH SPACE HUMIDITY LEVELS.
- d. AUTOMATIC SHUTDOWN:
- HVAC SYSTEMS SHALL BE EQUIPPED WITH AT LEAST ONE OF THE FOLLOWING CONTROLS THAT CAN START AND STOP THE SYSTEM UNDER DIFFERENT TIME SCHEDULES FOR SEVEN DIFFERENT DAY-TYPES PER WEEK, ARE CAPABLE OF RETAINING PROGRAMMING AND TIME SETTING DURING LOSS OF POWER FOR A PERIOD OF AT LEAST TEN HOURS, AND INCLUDE AN ACCESSIBLE MANUAL OVERRIDE OR EQUIVALENT FUNCTION, THAT ALLOWS TEMPORARY OPERATION OF THE SYSTEM FOR UP TO TWO HOURS.

SPECIFICATIONS

SECTION 0001 - NOTICE TO BIDDERS

1.1 BIDDERS REPRESENTATIONS

- A. THE BIDDER BY MAKING A BID REPRESENTS THAT:
- THE BIDDER HAS READ AND UNDERSTANDS THE BIDDING DOCUMENTS, TO THE EXTENT THAT SUCH DOCUMENTATION RELATES TO THE WORK FOR WHICH THE BID IS SUBMITTED, AND FOR OTHER PORTIONS OF THE PROJECT, IF ANY, BEING BID CONCURRENTLY OR PRESENTLY UNDER CONSTRUCTION.
- B. THE BID IS MADE IN COMPLIANCE WITH THE BIDDING DOCUMENTS.
- C. THE SPECIFICATIONS AND DRAWINGS ARE INTENDED TO SERVE JOINTLY AS A BASIS FOR THE BIDDER TO SUBMIT A CONTRACT PRICE FOR THE MATERIAL AND LABOR.
- D. SHOULD CONFLICTS OR DISCREPANCIES OCCUR WITHIN THE BIDDING DOCUMENTS, THE ITEM OR ITEMS IN DISPUTE THAT REPRESENT THE GREATER COST SHALL PREVAIL IN THE FINAL BID.
- E. THE BID IS BASED UPON THE MATERIALS, EQUIPMENT AND SYSTEMS REQUIRED BY THE BIDDING DOCUMENTS WITHOUT EXCEPTION.
- 1.2 EXISTING CONDITIONS AND COORDINATION

1.2 EXISTING CONDITIONS AND COORDINATION

- A. THE BIDDER HAS VISITED THE SITE, BECOME FAMILIAR WITH LOCAL CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED AND HAS CORRELATED THE BIDDER'S PERSONAL OBSERVATIONS WITH THE REQUIREMENTS OF THE PROPOSED BIDDING DOCUMENTS.
- B. THE BIDDER SHALL PROPOSE COORDINATION OF WORK SUCH THAT CONFLICTS WITH OTHER TRADES AND SPACE ALLOCATIONS ARE AVOIDED.

1.3 RESPONSIBILITIES

- A. THE BIDDER UNDERSTANDS THAT ANY CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR THE TIMELY COMPLETION AND ACCEPTANCE OF THEIR WORK AND THAT ANY ITEMS DAMAGED, LOST OR STOLEN DURING TIME OF CONSTRUCTION SHALL BE REPAIRED OR REPLACED WITHOUT ANY ADDITIONAL COST TO THE OWNER.
- B. THE BIDDER UNDERSTANDS THAT ANY PROPOSED WORK IN OCCUPIED TENANT SPACES SHALL BE PERFORMED DURING TIMES OF NON-TENANT OCCUPANCY OR AS SCHEDULED OR DIRECTED BY THE BUILDING MANAGER.
- C. THE BIDDER UNDERSTANDS THAT ANY PROPOSED SHUT-DOWN OF EXISTING SYSTEMS DURING CONSTRUCTION SHALL BE PRE-ARRANGED WITH THE BUILDING MANAGER AND THAT SUCH SHUT-DOWNS ARE TO BE KEPT TO A MINIMUM.

END OF SECTION 0001

SECTION 0101 - QUALITY OF WORK

1.1 WORKMANSHIP

- A. ALL WORK SHALL BE FREE FROM DEFECTS IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF FINAL ACCEPTANCE.
- B. ALL DEFECTS WHICH DEVELOP OR ARE DISCOVERED WITHIN THIS PERIOD SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE ARCHITECT OR BUILDING MANAGER AT NO ADDITIONAL COST TO THE OWNER.
- C. UPON COMPLETION OF THE WORK THE CONTRACTOR SHALL REMOVE FROM THE SITE, ALL TOOLS, DEMOLISHED APPLIANCES AND ANY SURPLUS MATERIAL.

1.2 CODE COMPLIANCE

- A. ALL WORK SHALL MEET ALL STATE AND LOCAL CODES HAVING JURISDICTION.

END OF SECTION 0101

SECTION 0102 –REQUIRED DOCUMENTS

1.1 SHOP DRAWINGS

- A. A SET OF PRINTS FOR ANY MECHANICAL WORK INCLUDING BUT NOT LIMITED TO, DUCTWORK AND PIPING LAYOUT SHALL BE SUBMITTED FOR APPROVAL TO THE ENGINEER PRIOR TO CONSTRUCTION OR PURCHASE OF MATERIALS.

1.2 SUBMITTALS

- A. EQUIPMENT SUBMITTALS OF ALL PROPOSED MECHANICAL AND ANCILLARY EQUIPMENT INCLUDING ALL ACCESSORIES SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW. ALL PERTINENT MODELS, SIZES, ACCESSORIES AND CHOICES SHALL BE CLEARLY CHECKED, PRINTED OR OTHERWISE INDICATED ON THE SUBMITTALS.

1.3 RECORD DRAWINGS

- A. UPON COMPLETION OF THE WORK, A RECORD DRAWING SHALL BE SUBMITTED TO THE OWNER DEPICTING ALL SUBSEQUENT CHANGES, ADDITIONS AND OR CORRECTIONS TO THE CONTRACT DRAWINGS AND OR CONTRACT SCOPE MADE DURING CONSTRUCTION. THIS DRAWING SHALL REPRESENT A COMPLETE RECORD OF THE WORK INSTALLED.



1.4 EQUIPMENT OPERATING INSTRUCTIONS

- A. ON COMPLETION AND ACCEPTANCE OF WORK, THIS CONTRACTOR SHALL FURNISH WRITTEN INSTRUCTIONS, EQUIPMENT MANUALS AND DEMONSTRATE TO THE OWNER THE PROPER OPERATION AND MAINTENANCE OF ALL EQUIPMENT AND APPARATUS FURNISHED UNDER THIS CONTRACT.
- B. THESE INSTRUCTIONS SHALL BE TYPED ON 8-1/2 IN. X 11 IN. PAPER AND BOUND IN THREE-RING BINDERS WITH CLEAR ACETATE COVERS. THE CONTRACTOR SHALL GIVE THREE COPIES OF THE INSTRUCTIONS TO THE OWNER AND ONE ELECTRONIC COPY TO THE ENGINEER.
- C. THE INSTRUCTION BOOKLET SHALL BE ORGANIZED IN SECTIONS, WITH ONE SECTION PER SYSTEM. THE COVER OF THE INSTRUCTION BOOKLET SHALL BEAR THE NAME, ADDRESS AND PHONE NUMBER OF THE PROJECT, ARCHITECT, ENGINEER, MECHANICAL CONTRACTOR AND SUBCONTRACTORS.



END OF SECTION 0102

[illegible]


PROJECT NUMBER: 22-097



3	PIPE SLEEVE THRU RATED WALL
M500.00	N.T.S




6	SUPPLY AIR DUCTWORK SUB-MAIN/BRANCH DUCT CONNECTION
M500.00	N.T.S




TYPICAL TRAPEZE HANGER SUPPORT

PIPE HANGER ROD AND SPACING SCHEDULE											
NOMINAL PIPE OR TUBE SIZE - INCHES	5/8	3/4	7/8	1	1 1/2	2	2 1/2	-	-	-	-
HANGER ROD SIZES INCHES	3/8	3/8	3/8	3/8	3/8	3/8	3/8	-	-	-	-
MAX. SPACING BETWEEN PIPE SUPPORTS - FEET	-	6	-	7	9	10	11	-	-	-	-
MAX. SPACING BETWEEN CU. TUBE SUPPORTS-FT.	6	6	6	6	8	9	10	-	-	-	-
NOTES : TRAPEZE HANGER SPACING SHALL BE BASED ON SPACING OF SMALLEST PIPE ON TRAPEZE. TRAPEZE SHALL BE DESIGNED WITH A FACTOR OF SAFETY OF 5 FOR CENTER OF SPAN CONCENTRATED LOAD.											




NOTE: LOCATE AIR GAP FITTING AND PIPING WITHIN SINK/LAVATORY ENCLOSURE.




1 METHOD OF HANGING REFRIGERANT PIPING
M501.00 N.T.S

2 AIR GAP FITTING DETAIL
M501.00 N.T.S


3 FUNNEL DRAIN INSTALLATION DETAIL
M501.00 N.T.S



4 CONDENSATE PUMP INSIDE CASING DETAIL
M501.00 N.T.S



5 A.C. UNIT INSTALLATION DETAIL
M501.00 N.T.S



6 FLEXIBLE CONNECTION (DUCT-EQUIPMENT)
M501.00 N.T.S




CHA CHA MATCHA
EMPIRE STORES


REVISIONS	
Δ ISSUE	DATE
PROJECT NUMBER: 22-097	

MECHANICAL
DETAILS (2 OF 3)

M501.00



1 DRIP PAN DETAIL
M502.00 N.T.S



2 MOTORIZED DAMPER DETAIL
M502.00 N.T.S


















CHA CHA MATCHA
EMPIRE STORES

REVISIONS	
Δ ISSUE	DATE
PROJECT NUMBER: 22-097	

MECHANICAL
DETAILS (3 OF 3)

M502.00

ELECTRICAL SYMBOLS LIST							GENERAL NOTES (APPLY TO ALL "E" DRAWINGS)	
SWITCHES AND CONTROLS		POWER AND TELECOMMUNICATION		ELECTRICAL ABBREVIATIONS			<div>1. ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH THE CURRENT VERSION OF THE NYC ELECTRICAL CODE, 2008 NEC WITH NYC AMENDMENTS, LOCAL JURISDICTION REQUIREMENTS, AND ALL GOVERNING LOCAL CODES, LAWS, AND REGULATIONS.</div> <div>2. CONTRACTOR SHALL VISIT THE SITE AND BECOME FAMILIAR WITH ALL EXISTING CONDITIONS THAT MAY AFFECT THE WORK. NO ADDITIONAL COMPENSATION WILL BE CONSIDERED FOR FAILURE TO DO SO.</div> <div>3. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS, TEST REPORTS, AND CERTIFICATIONS FOR TEMPORARY AND FINAL CERTIFICATE OF OCCUPANCY.</div> <div>4. FIRE STOP ALL PENETRATIONS OF FIRE RATED CONSTRUCTION IN A CODE APPROVED MANNER IN ORDER TO MAINTAIN FIRE RATING. ALL PENETRATIONS SHALL BE SLEEVED AND SEALED WATERTIGHT.</div> <div>5. SECURE ALL SUPPORTS TO BUILDING STRUCTURE UTILIZING TOGGLE BOLTS (HOLLOW MASONRY), EXPANSION SHIELDS OR INSERTS (CONCRETE AND BRICK), MACHINE SCREWS (METAL), BEAM CLAMPS (FRAMEWORK), WOOD SCREWS (WOOD) OR PAN THRU STRAPS (METAL DECK), NAILS, RAWL PLUGS AND WOOD PLUGS ARE NOT PERMITTED. WHERE REQUIRED BY STRUCTURE, PROVIDE THRU BOLTS AND FISH PLATES. SUPPORT HORIZONTAL RUNS OF METALLIC RACEWAYS NOT MORE THAN 10 FT APART. SUPPORT RACEWAY RISERS AT EACH FLOOR LEVEL. RUN EXPOSED RACEWAYS PARALLEL WITH OR AT RIGHT ANGLES TO WALLS.</div> <div>6. LEAVE WIRES WITH SUFFICIENT SLACK TO PERMIT MAKING FINAL CONNECTIONS. RACEWAYS OVER 10 FT LONG IN WHICH WIRING IS NOT INSTALLED: FURNISH FISH WIRE.</div> <div>7. VERIFY LOCATIONS OF OUTLETS AND SWITCHES IN FINISHED ROOMS WITH ARCHITECTURAL DRAWINGS OF INTERIOR DETAILS AND FINISH. IN CENTERING OUTLETS AND LOCATING BOXES AND OUTLETS, ALLOW FOR OVERHEAD PIPES, DUCTS AND MECHANICAL EQUIPMENT, EQUIPMENT, VARIATIONS IN FIREPROOFING AND PLASTERING, WINDOW AND DOOR TRIM, PANELING, HUNG CEILINGS AND THE LIKE. CORRECT ANY INACCURACY RESULTING FROM FAILURE TO DO SO WITHOUT EXPENSE TO OWNER.</div> <div>8. CONTRACTOR SHALL PROVIDE A WARRANTY ON ALL MATERIALS, EQUIPMENT, AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM THE DATE OF FINAL ACCEPTANCE.</div> <div>9. ALL UNUSED MATERIALS AND DEBRIS SHALL BE LEGALLY REMOVED AND DISPOSED OF AWAY FROM THE PREMISES ON A DAILY BASIS.</div> <div>10. CONTRACTOR SHALL PATCH, PAINT, AND RESTORE EXISTING SURFACES DAMAGED DURING THE COURSE OF THIS CONSTRUCTION TO PRE-EXISTING CONDITIONS OR BETTER.</div> <div>11. MINIMUM SIZE OF CONDUIT SHALL BE ¾", AND TYPE SHALL BE ELECTRICAL METALLIC TUBING (EMT), UNLESS OTHERWISE NOTED. PROVIDE NYLON DRAG LINE AND CONDUIT CAP FOR ALL EMPTY CONDUITS.</div> <div>12. CONNECT CONDUIT TO MOTOR CONDUIT TERMINAL BOXES WITH FLEXIBLE CONDUIT (MINIMUM 18 IN. LENGTH AND 50% SLACK). DO NOT TERMINATE IN OR FASTEN RACEWAYS TO MOTOR FOUNDATION.</div> <div>13. PULL AND JUNCTION BOXES WHERE INDICATED ON THE DRAWINGS, SHALL BE CONSIDERED SHOWN AT THEIR APPROXIMATE LOCATION. THE CONTRACTOR SHALL LOCATE THEM AS FIELD CONDITIONS DICTATE. ADDITIONAL PULL AND JUNCTION BOXES NOT SHOWN ON DRAWINGS SHALL BE PROVIDED WHERE REQUIRED BY APPLICABLE CODE PROVISIONS OR WHERE CALLED FOR BY FIELD CONDITIONS. PULL AND JUNCTION BOXES SHALL BE SURFACE TYPE, IN UNFINISHED AREAS AND INSTALLED CANCEALED IN FINISHED AREAS, AND ALL COVERS TO PULL & JUNCTION BOXES SHALL BE READILY ACCESSIBLE.</div> <div>14. SUPPORT PANEL, JUNCTION AND PULLBOXES INDEPENDENTLY TO BUILDING STRUCTURE WITH NO WEIGHT BEARING ON RACEWAYS.</div> <div>15. FOR EXACT LOCATION AND MOUNTING HEIGHT OF LIGHTING FIXTURES AND SWITCH/RECEPTACLE OUTLETS, REFER TO ARCHITECTURAL REFLECTED CEILING AND POWER PLANS.</div> <div>16. ALL ELECTRICAL ACCESSORIES AND EQUIPMENT INSTALLED OUTSIDE OR EXPOSED TO WEATHER SHALL HAVE NEMA 3R ENCLOSURES AND SHALL BE TIGHTLY GASKETED FOR A COMPLETE RAINIGHT INSTALLATION. ALL BUILDING EXTERIOR MOUNTED RECEPTACLES SHALL BE GFCI RATED AND MOUNTED IN WEATHERPROOF ENCLOSURE.</div> <div>17. ALL ACCESS PANEL LOCATIONS SHALL BE REVIEWED BY ARCHITECT PRIOR TO INSTALLATION.</div> <div>18. ELECTRICAL CONTRACTOR SHALL COORDINATE THE LOCATION AND INSTALLATION OF NEW WORK WITH THE GENERAL CONTRACTOR AND OTHER ASSOCIATED TRADES IN A TIMELY MANNER. THE CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL DIMENSIONS AND CONDITIONS PRIOR TO CONSTRUCTION. REFER TO ALL GENERAL, MECHANICAL, AND ELECTRICAL, DRAWINGS AND SPECIFICATIONS FOR THIS PROJECT.</div> <div>19. ALL CONDUITS AND EQUIPMENT TO BE CONCEAL ED IN FINISHED SPACES UNLESS OTHERWISE NOTED. CONDUITS SHALL BE ENCASED IN THE CONCRETE FLOOR SLAB.</div> <div>20. ALL EQUIPMENT AND MATERIALS INSTALLED IN PLENUM CEILINGS SHALL BE APPROVED FOR THAT APPLICATION.</div> <div>21. OUTLET BOXES AND JUNCTION BOXES ON OPPOSITE SIDES OF FIRE-RATED WALLS SHALL BE SEPARATED BY A HORIZONTAL DISTANCE OF NOT LESS THAN 24 INCHES, UNLESS FIRE-RATED BOXES OR PUTTY PADS ARE UTILIZED.</div> <div>22. COORDINATE ALL FLOOR PENETRATIONS WITH THE STRUCTURAL AND ARCHITECTURAL DRAWINGS. CONFIRM PENETRATION LOCATIONS WITHR THE ENGINEER AND OWNER BEFORE INSTALLATION.</div> <div>23. COORDINATE THE MOUNTING HEIGHT AND LOCATION OF RACEWAYS, COMMUNICATIONS OUTLETS, AND RECEPTACLES WITH THE ARCHITECTURAL CASEWORK DRAWINGS AND DETAILS. COORDINATE LOCATIONS OF LIGHT FIXTURES, SWITCHES, AND RELATED DEVICES WITH THE ARCHITECTURAL DRAWINGS AND DETAILS.</div> <div>24. REFER TO ARCHITECTURAL PLANS FOR FINAL LOACTIONS OF ALL LUMINARIES AND SWITCHES, AND FOR ALL FINISHED CEILING HEIGHTS.</div> <div>25. REFER TO ARCHITECTURAL PLANS FOR FINAL LOCATIONS OF ALL ELECTRICAL DEVICES, AND FOR FINAL CEILING AND WALL HEIGHTS AND LAYOUTS.</div> <div>26. LIGHTING FIXTURES PROVIDED WITH EMERGENCY BATTERY PACKS AND INDICATED WITH SWITCH CONTROL SHALL BE WIRED WITH BATTERY CHARGING/SENSING CIRCUIT WIRED AHEAD OF SWITCH CONTROL.</div> <div>27. NUMBER(S) SHOWN AT RECEPTACLES, JUNCTION BOXES AND EQUIPMENT INDICATES CIRCUIT NUMBERS IN PANELBOARD. PROVIDE WIRE AND CONDUIT TO INTERCONNECT EQUIPMENT AND DEVICES WITH SAME CIRCUIT NUMBERS AND RUN TO PANELBOARD.</div>	
WIRING SYSTEMS			JUNCTION BOX WITH BLANK COVER PLATE, CEILING MOUNTED..	A	AMPERES	EA		EACH
 POWER OR LIGHTING CIRCUITRY HOMERUN WITH PANELBOARD DESIGNATION, NUMBER WHERE USED INDICATES CIRCUIT NUMBER. IT SHALL CONSISTS OF 1#12 Ø, 1#12 N. & 1#12 G. IN 3/4"C, UNLESS OTHERWISE NOTED.			DUPLEX CONVENIENCE RECEPTACLE.	A/C, AC	AIR CONDITIONING UNIT	EC		EMPTY CONDUIT/ ELECTRICAL CONTRACTOR
			DUPLEX DEDICATED RECEPTACLE.	AF	AMPERE FRAME/AMP FUSE	EF		EXHAUST FAN
 POWER OR LIGHTING CIRCUITRY HOMERUN WITH PANELBOARD DESIGNATION, NUMBER WHERE USED INDICATES CIRCUIT NUMBER. IT SHALL CONSISTS OF 2#12 Ø, 2#12 N. & 2#12 G. IN 3/4"C, UNLESS OTHERWISE NOTED.			SPECIAL RECEPTACLE,VOLTAGE AND AMPERAGE BASED ON CONNECTED CIRCUIT.	AFF	ABOVE FINISHED FLOOR	EM		EMERGENCY
			TELEPHONE/DATA OUTLET, 4"SQURE OUTLET BOX WITH SINGLE GANG COLLAR AND BLANK PLATE. PROVIDE 3/4" E.C., U.O.N., UP TO HUNG CEILING AND TERMINATE WITH 90° ELBOW, BUSHING AND DRAG WIRE.	AS	AMP SWITCH	EMT		ELECTRICAL METALLIC TUBING
AIC	AMPS INTERRUPTING CAPACITY			EQUIP	EQUIPMENT			
AT	AMP TRIP			ER	EXISTING TO BE RELOCATED			
			DOUBLE DUPLEX RECEPTACLE – 20A–1P, 125V, NEMA 5–20R.	ATS	AUTOMATIC TRANSFER SWITCH	ETR		EXISTING TO REMAIN
			20A SPST TOGGLE SWITCH U.O.N. "a" DENOTES LIGHTING FIXTURE CONTROLLED.	AUTO	AUTOMATIC	EWF		ELECTRIFIED WORKSTATION FURNITURE
		ANNOTATION		AWG	AMERICAN WIRE GAUGE	EWH		ELECTRIC WATER HEATER
				C	CONDUIT	FA		FIRE ALARM
				C/B,CB	CIRCUIT BREAKER	FBO		FURNISHED BY OTHERS, INSTALLED & WIRED BY EC
				CKT	CIRCUIT	FDR		FEEDER
ELECTRICAL DRAWING LIST			KEYED NOTE REFERENCE	CLG	CEILING	FIBO		FURNISHED & INSTALLED BY OTHERS, WIRED BY EC
				COMM	COMMUNICATION	FIXT		FIXTURE
E–001.00	ELECTRICAL SYMBOLS LIST, ABBREVIATIONS & GENERAL NOTES		DETAIL REFERENCE: DETAIL NUMBER INDICATED ON TOP; DRAWING NUMBER INDICATED ON BOTTOM	CT	CURRENT TRANSFORMER	FL		FLOOR
E–002.00	ELECTRICAL SPECIFICATIONS SHEET 1 OF 2			CU	COPPER	FLUOR		FLUORESCENT
E–003.00	ELECTRICAL SPECIFICATIONS SHEET 2 OF 2		DISTRIBUTION PANELBOARD, 208V/120V–SURFACE MOUNTED.	*C	DEGREE CELSIUS	G		GROUND
E–101.00	ELECTRICAL LIGHTING PLAN			*F	DEGREE FAHRENHEIT	GFI		GROUND FAULT INTERRUPTER
E–201.00	ELECTRICAL POWER PLAN		NON FUSED DISCONNECT SWITCH AMPERAGE, AND NUMBER OF POLES AS NOTED.	DIA	DIAMETER	GP		GENERAL PURPOSE
E–301.00	ELECTRICAL DETAILS			DISC	DISCONNECT	HC		HUNG CEILING
E–401.00	ELECTRICAL RISER DIAGRAM & PANEL SCHEDULE			DN	DOWN	HP		HORSEPOWER
				DP	DISTRIBUTION PANEL	HWH		HOW WATER HEATER
				DWH	DOMESTIC WATER HEATER	HZ		HERTZ
				DWG	DRAWING	IC		INTERRUPTING CAPACITY
				JB	JUNCTION BOX	PP		POWER PANEL
				KCMIL	ONE THOUSAND CIRCULAR MILS	PVC	POLYVINYL CHLORIDE	
		KV	KILOVOLT	PWR	POWER			
		KVA	KILOVOLT–AMPERES	R	REMOVE			
		KW	KILOWATTS	RE	RELOCATED EXISTING			
		LP	LIGHTING PANEL	REC	RECEPTACLE			
		LTG	LIGHTING	RGS	RIGID GALVANIZED STEEL			
		MAX	MAXIMUM	RR	REMOVE & RELOCATE			
		MC	MOTOR CONTROLLER	SECT	SECTION			
		MCB	MAIN CIRCUIT BREAKER	SPDT	SINGLE POLE DOUBLE THROW			
		MER	MECHANICAL EQUIPMENT ROOM	SPST	SINGLE POLE SINGLE THROW			
		MIN	MINIMUM	SPEC	SPECIFICATION			
		MLO	MAIN LUGS ONLY	SW	SWITCH			
		MTD	MOUNTED	SWBD	SWITCHBOARD			
		MTS	MANUAL TRANSFER SWITCH	SYM	SYMMETRICAL			
		N	NEUTRAL	SYS	SYSTEMS			
		NE	NEW DEVICE TO REPLACE EXISTING	TELE	TELEPHONE			
		NIC	NOT IN CONTRACT	TEMP	TEMPERATURE			
		NL	NIGHT LIGHT	TXF	TOILET EXHAUST FAN			
		NTS	NOT TO SCALE	TYP	TYPICAL			
		OC	ON CENTER	UON	UNLESS OTHERWISE NOTED			
		P	POLES	V	VOLT/VOLTAGE			
		PB	PULLBOX	VA	VOLT AMPERE			
		PC	PERSONAL COMPUTER	VAV	VARIABLE AIR VOLUME			
		ø	PHASE	VFD	VARIABLE FREQUENCY DRIVE			
		PNL	PANEL	VP	VAPORPROOF			
		W	WATT	WP	WEATHER PROOF			
		W	WIRE	XFMR	TRANSFORMER			
		WH	WALL HEATER	ZRT	ZONE REGISTER TERMINALS			
		E	EXISTING	IG	ISOLATED GROUND			

Cha Cha
MATCHA

CHA CHA MATCHA
EMPIRE STORES

[illegible]

PROJECT NUMBER: 22-097

ELECTRICAL SYMBOL LIST, ABBREVIATIONS & GENERAL NOTES

E001.00

ELECTRICAL SPECIFICATIONS

- | | | |
|---|--|---|
| <p>GENERAL: A. THE "GENERAL CONDITIONS OF THE CONTRACT FOR CONSTRUCTION," AS DOCUMENT, LATEST EDITION, AND THESE SPECIFICATIONS AS APPLICABLE ARE PART OF THIS CONTRACT.</p> <p>B. DRAWING ARE DIAGRAMMATIC AND INDICATE GENERAL ARRANGEMENT OF SYSTEMS AND WORK. CONDUIT ROUTING IS SHOWN DIAGRAMMATICALLY AND DOES NOT SHOW JOINTS, OFFSETS, DROPS AND RISES OF RUNS. THE CONTRACTOR SHALL ALLOW IN HIS PRICE FOR ROUTING OF CONDUIT TO AVOID OBSTRUCTIONS. COORDINATION WITH EXISTING SERVICES, INCLUDING THOSE OF OTHER TRADES, IS REQUIRED, MAINTAIN HEADROOM AND SPACE CONDITIONS.</p> <p>C. BIDDERS, BEFORE SUBMITTING PROPOSALS, SHALL VISIT AND CAREFULLY EXAMINE THE AREA AFFECTED BY THIS WORK TO FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS AND THE DIFFICULTIES THAT WILL ATTEND THE EXECUTION OF THIS WORK. SUBMISSION OF A PROPOSAL WILL BE CONSTRUED AS EVIDENCE THAT SUCH AN EXAMINATION HAS BEEN MADE, AND LATER CLAIMS WILL NOT BE RECOGNIZED FOR EXTRA LABOR, EQUIPMENT, OR MATERIALS, REQUIRED BECAUSE OF DIFFICULTIES ENCOUNTERED WHICH COULD HAVE BEEN FORESEEN HAD SUCH AN EXAMINATION BEEN MADE.</p> <p>D. INSTALL WORK SO AS TO BE READILY ACCESSIBLE FOR OPERATION, MAINTENANCE AND REPAIR, MINOR DEVIATIONS FROM DRAWING MAY BE MADE TO ACCOMPLISH THIS, BUT CHANGES WHICH INVOLVE EXTRA COST SHALL NOT BE MADE WITHOUT APPROVAL.</p> <p>E. REMOVAL AND RELOCATION OF CERTAIN EXISTING WORK MAY BE NECESSARY FOR THE PERFORMANCE OF THE GENERAL WORK. ALL EXISTING CONDITIONS CANNOT BE COMPLETELY DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL SURVEY THE SITE AND INCLUDE ALL CHANGES AND CHARGES IN MAKING UP THE WORK PROPOSAL.</p> <p>F. CONNECTIONS TO EXISTING WORK: INSTALL NEW WORK AND CONNECT TO EXISTING WORK WITH MINIMUM INTERFERENCE TO EXISTING FACILITIES. TEMPORARY SHUTDOWNS OF EXISTING SERVICES SHALL BE PERFORMED AT NO ADDITIONAL CHARGES. AT TIMES NOT TO INTERFERE WITH NORMAL OPERATION OF EXISTING FACILITIES AND ONLY WITH WRITTEN CONSENT OF OWNER, ALARM AND EMERGENCY SYSTEMS SHALL NOT BE INTERRUPTED. MAINTAIN CONTINUOUS OPERATION OF EXISTING FACILITIES AS REQUIRED WITH NECESSARY TEMPORARY CONNECTIONS BETWEEN NEW AND EXISTING WORK. CONNECT NEW WORK TO EXISTING WORK IN A NEAT AND ACCEPTABLE MANNER. RESTORE EXISTING DISTURBED WORK TO ORIGINAL CONDITION, INCLUDING MAINTENANCE OF WIRING CONTINUITY AS REQUIRED.</p> <p>G. DISCONNECT, REMOVE AND/OR RELOCATE EXISTING MATERIAL, EQUIPMENT AND OTHER WORK AS NOTED OR REQUIRED FOR PROPER INSTALLATION OF NEW WORK.</p> <p>H. THE CONTRACTOR SHALL KEEP ALL EQUIPMENT AND MATERIALS, AND ALL PARTS OF THE BUILDING EXTERIOR SPACES AND ADJACENT STREETS, SIDEWALKS AND PAVEMENTS, FREE FROM MATERIAL AND DEBRIS RESULTING FROM THE EXECUTION OF THE WORK. EXCESS MATERIALS WILL NOT BE PERMITTED TO ACCUMULATE EITHER ON THE INTERIOR OR THE EXTERIOR.</p> <p>I. SEAL OPENINGS THROUGH PARTITIONS, WALLS AND FLOORS WITH MINERAL WOOL OR OTHER NONCOMBUSTIBLE MATERIAL, UNLESS OTHERWISE NOTED.</p> <p>J. PROVIDE ALL NECESSARY FLASHING AND COUNTER FLASHING TO MAINTAIN THE WATERPROOFING INTEGRITY OF THE BUILDING AS REQUIRED BY THE INSTALLATION OR REMOVAL OF CONDUIT AND EQUIPMENT, PROVIDE EQUIPMENT CURBS AS REQUIRED.</p> <p>K. ALL EXISTING MATERIAL, EQUIPMENT AND CONSTRUCTION DEBRIS TO BE REMOVED UNDER THIS CONTRACT SHALL BECOME THE PROPERTY OF THE CONTRACTOR WITH THE EXCEPTION OF SPECIFIC EQUIPMENT AND APPARATUS REQUESTED BY THE BUILDING REPRESENTATIVE. ARCHITECT OR AS NOTED TO BE RELOCATED ON THE DRAWINGS. REMOVED EQUIPMENT SHALL BE PROPERLY DISPOSED OF BY THIS CONTRACTOR.</p> <p>L. THE CONTRACTOR'S PROPOSAL FOR ALL WORK SHALL BE PREDICATED ON THE PERFORMANCE OF THE WORK DURING REGULAR WORKING HOURS. WHEN SO DIRECTED, HOWEVER, THE CONTRACTOR SHALL INSTALL WORK DURING OVERTIME HOURS AND THE ADDITIONAL COST TO BE CHARGED THEREFORE SHALL BE ONLY THE "PREMIUM" PORTION OF THE WAGES PAID.</p> <p>M. UNLESS OTHERWISE SPECIFICALLY NOTED OR SPECIFIED, INCLUDE ALL CUTTING AND PATCHING OF EXISTING FLOORS, WALLS, PARTITIONS AND OTHER MATERIALS IN THE EXISTING BUILDING. THE CONTRACTOR SHALL RESTORE THESE AREAS TO ORIGINAL CONDITION.</p> <p>N. ALL MATERIAL AND EQUIPMENT SHALL BE NEW UNLESS OTHERWISE NOTED AND SHALL BE IN ACCORDANCE WITH BUILDING STANDARDS.</p> <p>O. INSURANCE: PROVIDE IN ACCORDANCE WITH OWNER/BUILDING REQUIREMENTS AND SHALL INCLUDE A HOLD HARMLESS CLAUSE FOR OWNER AND ENGINEER.</p> <p>P. THE FINAL ACCEPTANCE SHALL BE MADE AFTER THE CONTRACTOR HAS ADJUSTED HIS EQUIPMENT, TESTED THE VARIOUS SYSTEMS, DEMONSTRATED THAT IT FULFILLS THE REQUIREMENTS OF THE DRAWINGS AND SPECIFICATIONS AND HAS FURNISHED ALL THE REQUIRED CERTIFICATED OF INSPECTION AND APPROVAL.</p> | <p>2. GUARANTEE: ALL MATERIALS AND WORKMANSHIP SHALL BE GUARANTEED AS FATHED IN PARAGRAPH 2.C.</p> <p>3) CURRENT CHARACTERISTICS:</p> <p>a. SERVICE: 120/208 VOLT, 3 PHASE, 4 WIRE, 60 HERTZ WITH GROUNDED NEUTRAL.</p> <p>b. DISTRIBUTION: 120/208 VOLT, 3 PHASE, 4 WIRE, 60 HERTZ WITH GROUNDED NEUTRAL.</p> <p>4) HEIGHTS OF OUTLETS:</p> <p>a. FROM FINISHED FLOOR TO CENTERLINE OF OUTLETS FOR:</p> <ul style="list-style-type: none"> RECEPTABLES AND TELEPHONES: 1 FT-6 IN. WALL SWITCHES: 4 FT-0 IN. WALL FIXTURES: 7 FT-0 IN. MOTOR CONTROLLERS: 5 FT-0 IN. CLOCKS: 7 FT 6 IN <p>b. EXCEPTIONS: AT JUNCTION OF DIFFERENT WALL FINISH MATERIALS, ON MOLDING OR BREAK IN WALL SURFACE, IN VIOLATION OF CODE, OR AS NOTED OR DIRECTED.</p> <p>D. PRODUCT DELIVERY, STORAGE AND HANDLING</p> <p>1) MOVING OF EQUIPMENT: WHERE NECESSARY, SHIP IN CARTED SECTIONS OF SIZE TO PERMIT PASSING THROUGH AVAILABLE SPACES.</p> <p>2) ACCESSIBILITY: FOR OPERATION, MAINTENANCE AND REPAIR, MINOR DEVIATIONS SHALL BE PERMITTED, CHANGES OF MAGNITUDE OR INVOLVING EXTRA COST ARE NOT PERMISSIBLE WITHOUT REVIEW. GROUP CONCEALED ELECTRICAL EQUIPMENT REQUIRING ACCESS WITH EQUIPMENT FREELY ACCESSIBLE THROUGH ACCESS DOORS.</p> <p>E. MATERIALS</p> <p>1) NAMEPLATES: PROVIDE BLACK LAMICOID SHEET WITH 3/4 IN. WHITE LETTERING, FASTENED WITH EPOXY CEMENT FOR EACH DISCONNECT SWITCH, CIRCUIT BREAKER, PANEL, CABINET, TRANSFORMER, ENCLOSURE, MOTOR CONTROLLER AND THE LIKE. NAMEPLATES SHALL DESCRIBE THE NAME AND NUMBER OF EACH COMPONENT.</p> <p>2) CABLE TAGS: TAG EACH CONDUCTOR PASSING THROUGH SPLICE OR PULLBOX WITH A WHITE LINEN TAG, INDICATING POINT OF ORIGIN AND TERMINATION OF THE CIRCUIT.</p> <p>3) INSERTS AND SUPPORTS:</p> <p>a. INSERTS: STEEL, SLOTTED TYPE, FACTORY PAINTED.</p> <ul style="list-style-type: none"> SINGLE ROD: SIMILAR TO GRINNELL FIG. 281. MULTI-ROD: SIMILAR TO FEE AND MASON SERIES 9000 WITH END CAPS AND CLOSURE STRIPS. CLIP FORM NAILS FLUSH WITH INSERTS. MAXIMUM LOADING 75 PERCENT OF RATING. <p>b. SUPPORTS FROM BUILDING CONSTRUCTION: INSERTS, BEAM CLAMPS, STEEL FISHPLATES (IN CONCRETE FILL ONLY), CANTILEVER BRACKETS OR OTHER MEANS. SUBMIT FOR REVIEW.</p> <p>c. GROUPED LINES AND SERVICES: TRAPEZE HANGERS OF BOLTED ANGLES OR CHANNELS.</p> <p>d. WHERE BUILDING CONSTRUCTION IS INADEQUATE: PROVIDE ADDITIONAL FRAMING. SUBMIT FOR REVIEW.</p> <p>F. PAINT SHALL BE THE BEST GRADE FOR ITS PURPOSE. DELIVER IN ORIGINAL SEALED CONTAINERS AND APPLY IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. COLORS SHALL BE AS SELECTED BY ARCHITECT OR ENGINEER. UTILIZE GALVANIZED STEEL PRIMER ON PANEL AND PULL BOXES. AFTER FABRICATION, UTILIZE HOT DIPPED GALVANIZED OR DIPPED IN ZINC BASED PRIMER FOR: OUTLET BOXES, JUNCTION BOXES, CONDUIT HANGERS, RODS, INSERTS AND SUPPORTS. ZINC BASED PRIMER WITH FINISH TO MATCH SURROUNDINGS SHALL BE USED FOR MARKED SURFACES OF STEEL EQUIPMENT AND RACEWAYS. A FIELD-APPLIED ZINC BASED PRIME COAT SHALL BE UTILIZED FOR STEEL OR IRONWORK.</p> <p>G. BRUSH AND CLEAN WORK PRIOR TO CONCEALING, PAINTING AND ACCEPTANCE. PAINTED EXPOSED WORK SOILED OR DAMAGED; CLEAN AND REPAIR TO MATCH ADJOINING WORK BEFORE FINAL ACCEPTANCE. REMOVE DEBRIS FROM INSIDE AND OUTSIDE OF MATERIAL AND EQUIPMENT.</p> <p>H. FINAL LOCATIONS AND MOUNTING ORIENTATIONS OF ALL SWITCHES, RECEPTABLES AND LIGHT FIXTURES SHALL BE VERIFIED WITH ARCHITECT.</p> <p>I. ALL ACCESS DOOR LOCATIONS SHALL BE REVIEWED BY ARCHITECT PRIOR TO INSTALLATION.</p> | <p>4. SHOP DRAWINGS</p> <p>A. PRIOR TO THE INSTALLATION OF ANY WORK AND PROCUREMENT OF EQUIPMENT, THE CONTRACTOR SHALL PROVIDE COMPLETE SETS OF COORDINATED SHOP DRAWINGS OF ALL NEW AND EXISTING EQUIPMENT, INDICATING CAPACITY, DIMENSIONS AND SEQUENCE OF OPERATION FOR WRITTEN APPROVAL BY THE ARCHITECT AND ENGINEER.</p> <p>B. INDICATE ON EACH SHOP DRAWINGS SUBMITTED:</p> <ol style="list-style-type: none"> PROJECT NAME AND LOCATION NAME OF ARCHITECT AND ENGINEER ITEM IDENTIFICATION APPROVAL STAMP OF PRIME CONTRACTOR <p>C. SUBMISSIONS:</p> <ol style="list-style-type: none"> SUBMISSIONS 11 IN. X 17 IN. OR SMALLER: IF THE SUBMISSION IS A CATALOG CUT, THEN THE CONTRACTOR SHALL SUBMIT ONE ORIGINAL AND TWO COPIES. OTHERWISE, HE SHALL SUBMIT THREE COPIES. THE ARCHITECT WILL FORWARD THE ORIGINAL AND ONE COPY (TWO COPIES WHEN NO ORIGINAL IS RECEIVED) TO THE ENGINEER. ALL CATALOG CUTS SHALL BE COMPLETE. SUBMISSIONS LARGER THAN 11 IN. X 17 IN.: SUBMIT TWO PRINTS AND ONE PAPER SEPIA TO THE ARCHITECT. THE ARCHITECT WILL FORWARD ONE PRINT AND THE PAPER SEPIA TO THE ENGINEER. <p>D. SUBMIT SHOP DRAWINGS FOR THE FOLLOWING:</p> <ol style="list-style-type: none"> SAFETY/DISCONNECT SWITCHES FUSES CIRCUIT BREAKERS PANEL BOARDS/LOAD CENTER (INCLUDING DIMENSIONS, SCHEDULES, AND CATALOG CUTS). RACEWAYS WIRE AND CABLE WALL SWITCHES INSERTION RECEPTABLES MOMENTARY CONTACT SWITCHES TIME SWITCHES LIGHTING FIXTURES. <p>E. ASSIST AND PROVIDE ALL NECESSARY INFORMATION, DIAGRAMS, SKETCHES, ETC., TO THE HVAC CONTRACTOR, FOR THE PREPARATION OF COORDINATED SHOP DRAWINGS INDICATING ROUTING OF FEEDERS, CONTROL CONDUTS, RECESSED FIXTURES AND ADJACENT NEARBY PIPING AND DUCTWORK WHERE APPLICABLE, CERTIFIED BY ALL TRADES THAT COORDINATION HAS BEEN ESTABLISHED. SUBMIT FOUR(4) BOOKBOUND OPERATING AND SERVICE MANUALS WHICH SHALL INCLUDE COPIES OF ALL SHOP DRAWING, PROVIDE SHOP DRAWINGS FOR PANELS, FIXTURES, WIRING DEVICES, CONDUIT, CABLE, DISCONNECT SWITCH, RELAYS, CONTRACTORS, AND OTHER SYSTEMS AS DIRECTED BY THE ENGINEER.</p> <p>5. AS-BUILT DRAWINGS AND EQUIPMENT OPERATIONAL INSTRUCTIONS</p> <p>A. UPON COMPLETION AND ACCEPTANCE OF WORK, CONTRACTOR SHALL FURNISH WRITTEN INSTRUCTIONS AND EQUIPMENT MANUALS AND DEMONSTRATE TO THE OWNER THE PROPER OPERATION AND MAINTENANCE OF ALL EQUIPMENT AND APPARATUS FURNISHED UNDER THIS CONTRACT.</p> <p>B. THESE INSTRUCTIONS SHALL BE TYPED ON 8-1/2 IN. X 11 IN. PAPER AND BOUND IN THREE RING BINDERS WITH CLEAR ACETATE COVERS. CONTRACTOR SHALL GIVE THREE COPIES OF THE INSTRUCTIONS TO THE OWNER AND ONE COPY TO THE ENGINEER.</p> <p>C. THE INSTRUCTION BOOKLET SHALL BEAR THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE PROJECT, ARCHITECT AND ENGINEER.</p> <p>D. REPRODUCIBLE "AS-BUILT" DRAWINGS SHALL BE PROVIDED INDICATING THE AS INSTALLED CONDITIONS OF THE WORK. "AS-BUILT" DRAWINGS SHALL BE PROVIDED TO THE ARCHITECT AFTER COMPLETION OF THE INSTALLATION.</p> <p>6. LOW-VOLTAGE DISTRIBUTION EQUIPMENT:</p> <p>A. PROVIDE COMPLETE EQUIPMENT INCLUDING: SWITCHES, FUSES, CIRCUIT BREAKERS, PANELS AND TRANSFORMERS.</p> <p>B. ALL EQUIPMENT SHALL CONFORM TO NEMA, ANSI AND IEEE STANDARDS.</p> <p>C. DISCONNECT SWITCHES SHALL BE FUSED OR NONFUSED AS NOTED. VOLTAGE SHALL BE AS REQUIRED. SWITCHES SHALL BE HEAVY DUTY, EXCEPT AS NOTED, AND HIGHER POWER RATED FOR MOTOR LOADS. TOGGLE TYPE SWITCHES SHALL BE NONFUSED, LOAD BREAK, HAVING MAXIMUM RATINGS OF 20 AMP AT 600 VOLTS AND 30 AMP AT 240 VOLTS. TWO-POLE SWITCHES SHALL BE SIMILAR TO HART AND HEGEMAN NO. 6806F. THREE-POLE SWITCHES SHALL BE SIMILAR TO HART AND HEGEMAN NO. 7810F. KNIFE-BLADE TYPE SWITCHES SHALL BE LOAD BREAK, QUICK-MAKE- QUICK-BREAK, UL CLASS R UP TO 600 AMP. MAXIMUM RATING EXCEPT AS NOTED SHALL BE 800 AMP. ARC QUENCHERS SHALL BE PROVIDED. SWITCHES SHALL BE SIMILAR TO GENERAL ELECTRIC QMR. ALL SWITCH ENCLOSURES SHALL BE DEAD FRONT, NEMA TYPE 1, EXCEPT AS NOTED.</p> <p>7. DISTRIBUTION PANEL BOARDS, CIRCUIT BREAKER TYPE:</p> <p>A. THREE PHASE, 4 OR 5 WIRE, COPPER BUS BARS, WITH 2, 3, OR 4 WIRE BRANCHES, AS NOTED, CAPACITY OF PANEL AND CIRCUITS, AS NOTED BELOW. PANEL BOARD TO HAVE GROUND BUS SAME SIZE AS PHASE BUSES.</p> <p>B. CABINETS: CODE GAUGE GALVANIZED SHEET STEEL PRIMED AND PAINTED WITH TRIM AND DOOR. TYPE AS NOTED, LAP AND RIVET CORNERS OR FORM AS APPROVED.</p> <p>C. TRIM: ONE PIECE FULL FINISH PRIMED AND PAINTED SHEET STEEL. TRIM SHALL BE MOUNTED WITH A CONTINUOUS PIANO HINGE CONFIGURED IN SUCH A MANNER THAT IT SHALL BE POSSIBLE TO GAIN FULL ACCESS TO CIRCUIT BREAKERS AND WIRING GUTTERS WITHOUT REMOVING THE TRIM. PROVIDE A MULTI-PIN CYLINDER LOCK (YALE, CORBIN OR EQUAL) TO LATCH THE TRIM. KEYS SHALL BE MILLED.</p> <p>D. HARDWARE: MULTI-PIN, CYLINDER LOCKS WITH MILLED KEYS. ALL PANELS SHALL BE KEYS ALIKE. DOOR OVER 48" HIGH SHALL BE EQUIPPED WITH A CHROME PLATED VAULT HANDLE, BUILT-IN LOCK AND 3-POINT CATCH FASTENING DOOR AT TOP, BOTTOM AND CENTER.</p> <p>E. HINGES: CONCEALED, CONTINUOUS PIANO HINGE AS DESCRIBED ABOVE.</p> |
|---|--|---|

SHORT CIRCUIT RATING 25,000 AMPERES, RMS SYMMETRICAL FOR ALL 120/208V APPLICATIONS. INDIVIDUAL CIRCUIT BREAKERS SHALL HAVE MINIMUM 100A FRAME, TRIPS SIZED AS SHOW ON THE PLANS.

- I. MINIMUM GUTTER SPACES: PANELS WITH 225 AMPERE MAINS, 5-3/4" MINIMUM, 400 AMPERES AND OVER, MINIMUM GUTTERS 8". FOR PANELS WITH THROUGH FEEDERS, INCREASE GUTTER WIDTH BY 2". MINIMUM. AND PROVIDE A SHEET STEEL BARRIER BETWEEN THE PANEL GUTTER AND THE THROUGH FEEDER PORTION OF THE BACK BOX. BRANCH CIRCUIT BREAKERS SHALL BE MECHANICALLY INTERLOCKED WHEN SHOWN ON DRAWINGS.
- J. DISTRIBUTION AND SUB-DISTRIBUTION PANEL BOARDS SHALL BE A MINIMUM OF 30" WIDE AND 10" DEEP.
- K. PANEL BOARD SHALL HAVE MAIN CIRCUIT BREAKER OR MAIN LUGS AS INDICATED ON THE DRAWINGS. QUANTITY, POLES AND TRIP RATINGS OF BRANCH CIRCUIT BREAKERS TO BE AS INDICATED ON DRAWINGS.
- L. PANEL BOARD SHALL HAVE ENGRAVED WHITE CORE, BLACK LAMACOID NAMEPLATE SCREWED ONTO PANE TRIM WITH DESIGNATION LABEL (PANEL BOARD NAME, VOLTAGE, RATING OR MAINS IN AMPS).
- A. MATERIALS
- 1) RACEWAYS:
- a. RIGID STEEL CONDUIT: FULL-WEIGHT PIPE, GALVANIZED, THREADED.
 - b. ELECTROMETALLIC TUBING (EMT): THIN WALL PIPE, GALVANIZED, THREADESS.
 - c. FLEXIBLE STEEL CONDUIT: CONTINUOUS SINGLE STRIP, GALVANIZED.
 - d. WIREWAYS: WIRE SHALL BE AS NOTED, MINIMUM NO. 16 GAUGE STEEL WITH GROUND CONTINUITY. FINISH SHALL BE BAKED ENAMEL. COVERS SHALL BE SCREW-ON.
 - e. SURFACE METAL RACEWAY: SIZE AS NOTED. BASE 0.04 IN., COVER 0.25 IN. MATERIAL SHALL BE STEEL FINISH SHALL BE BAKED ENAMEL. COVERS SHALL BE SCREW-ON.
- 2) FITTINGS AND ACCESSORIES:
- a. RIGID STEEL: NONSPILT, THREADED, STEEL OR MALLEABLE IRON. ZINC DIE CAST NOT PERMITTED.
 - b. ELECTROMETALLIC TUBING: COMPRESSION TYPE. GALVANIZED RIGID STEEL ELBOWS, 2 IN. OR LARGER.
 - c. FLEXIBLE METALLIC CONDUIT: ANGLE WEDGE TYPE WITH INSULATED THROAT.
 - d. BUSHINGS: METALLIC INSULATED TYPE.

- 2) FITTINGS AND ACCESSORIES:
- a. RIGID STEEL: NONSPLIT, THREADED, STEEL OR MALLEABLE IRON ZINC DIE CAST NOT PERMITTED.
 - b. ELECTROMETALLIC TUBING: COMPRESSION TYPE. GALVANIZED RIGID STEEL ELBOWS, 2 IN. OR LARGER.
 - c. FLEXIBLE METALLIC CONDUIT: ANGLE WEDGE TYPE WITH INSULATED THROAT.
 - d. BUSHINGS: METALLIC INSULATED TYPE.



CHA CHA MATCHA
EMPIRE STORES

[illegible]

PROJECT NUMBER: 22-097

**ELECTRICAL
SPECIFICATIONS
SHEET 1 OF 2**

E002.00



ELECTRICAL POWER PLAN | 1

1/4" = 1'-0"

POWER PLAN GENERAL NOTES

- ALL 120V, 15A AND 20A RECEPTACLES IN KITCHEN AREA SHALL BE "GFCI" IN ACCORDANCE WITH NEC ARTICLE 210.8(B). PROVIDE GFI RATED BREAKER AT PANEL FOR KITCHEN EQUIPMENT.
- VERIFY MOUNTING HEIGHTS OF ALL RECEPTACLES WITH EQUIPMENT SUPPLIER/ARCHITECT PRIOR TO INSTALLATION.
- ELECTRICAL CONTRACTOR TO PROVIDE CORD & PLUG CONNECTIONS FOR EQUIPMENT AS REQUIRED.
- ELECTRICAL CONTRACTOR TO COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION AND ALL THE ELECTRICAL REQUIREMENTS FOR THE SPECIAL EQUIPMENTS.
- E.C. SHALL VERIFY THE CIRCUIT FOR EXISTING & NEW EQUIPMENTS IN FIELD. UPDATE CIRCUIT NUMBER IF REQUIRED AS PER SITE CONDITION. BASE BID ACCORDINGLY.

POWER PLAN - KEYED WORK NOTES

- ALL EXISTING HVAC EQUIPMENTS AND ITS ELECTRICAL CONNECTIONS SHALL REMAIN. E.C. SHALL VERIFY THE OPERABLE CONDITION OF EXISTING ELECTRICAL CONNECTION IN FIELD. REPLACE IF FOUND INOPERABLE BASE BID ACCORDINGLY.
- ELECTRICAL CONTRACTOR TO COORDINATE WITH ARCHITECT/OWNER FOR POS EQUIPMENTS AND FURTHER INFORMATION REGARDING POS AND UNDER COUNTER ELECTRICAL SERVICE.
- NEW 40 AMPS, 120/208V, 3-PHASE ELECTRICAL PANEL "RP-B" FOR THE PROJECT SPACE. E.C. TO COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD.
- NEW 15 KVA 480/277V TO 208/120V, 3-PHASE STEP DOWN TRANSFORMER FOR THE PROJECT SPACE. E.C. TO COORDINATE WITH OWNER/ARCHITECT FOR EXACT LOCATION IN FIELD.
- EXISTING 100 AMPS, 120/208V, 3-PHASE ELECTRICAL PANEL "RP-A" SHALL REMAIN. E.C. TO FIELD VERIFY EXACT RATING, SIZE & OPERABLE CONDITION OF EXISTING PANEL "RP-A". INFORM ENGINEER FOR ANY DISCREPANCY. COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD. BASE BID ACCORDINGLY.
- EXISTING 100 AMPS, 480/277V, 3-PHASE ELECTRICAL PANEL "HPP" SHALL REMAIN. E.C. TO FIELD VERIFY EXACT RATING, SIZE & OPERABLE CONDITION OF EXISTING PANEL "HPP". INFORM ENGINEER FOR ANY DISCREPANCY. COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD. BASE BID ACCORDINGLY.
- ELECTRICAL CONTRACTOR SHALL COORDINATE WITH ARCHITECT/OWNER FOR THE EXACT LOCATION OF ANGEL JUICER (#21) & ELECTRICAL BREWING KETTLE (#22).
- JUNCTION BOX FOR SIGNAGE LIGHTING. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH OWNER/ARCHITECT FOR THE EXACT LOCATION OF THE SIGNAGE IN FIELD.

KITCHEN EQUIPMENT SCHEDULE

KITCHEN EQUIPMENT SCHEDULE							
ITEM NO.	QTY.	DESCRIPTION	MANUFACTURER/PRODUCT NO.	VOLTAGE	PHASE	AMPS	kW
1A	1	ICE MAKER	ICEOMATIC MODEL NO. CIM1136HA	208	1	13.9	2.89
2	1	LOW TEMP DISHWASHER	ECOLAB / E-ULT	120	1	15	1.80
3B	2	MM BOILER UNIT	MAVAM / CUSTOM	208	1	20	4.16
4B	2	STEAM UNIT	MAVAM / CUSTOM	208	1	17	3.54
5A	1	UC FRIDGE - 1 DOOR	HOSHIZAKI / UR27B	115	1	2.5	0.29
5B	1	SOFT SERVE FREEZER	TAYLOR / C161	208	1	12	2.50
6	1	UNDER COUNTER FRIDGE - 2 DOOR	TURBO AIR / MUR-48-N	115	1	2.4	0.28
7	1	UNDER COUNTER FRIDGE - 3 DOOR	TURBO AIR / MUR-72-N	115	1	2.5	0.29
8	2	POS	TOAST / FLEX	110	-	-	-
9	1	UNDER COUNTER GRAB AND GO FRIDGE	STRUCTURAL CONCEPTS / CO33R	115	1	12	1.38
11B	1	GLYCOL PUMP	MICROMATIC / MMP P4301	115	1	17.7	2.04
21	1	ANGEL JUICER	BY OWNER/ MODEL NO. AG-8500	120	1	5.8	0.70
22	1	ELECTRICAL BREWING KETTLE	BY OWNER/ MODEL NO.35L	208	1	13	2.70
23	1	COMMERCIAL FOOD BLENDER	VITAMIX/ MODEL NO. 62826	120	1	13	1.56
24	1	CONVEYOR TOASTER	VOLLRATH / CT2H-120250	120	1	13.3	1.60
27	1	SCALE	ACAIA SCALE	120	1	1.5	0.18



CHA CHA MATCHA
EMPIRE STORES


REVISIONS	
Δ ISSUE	DATE

PROJECT NUMBER: 22-097

ELECTRICAL
POWER PLAN


E201.00

NOTE:
THIS INFORMATION MAY NOT CONTAIN ALL DETAILS
REQUIRED FOR CONSTRUCTION. APPROPRIATE MODIFICATION
MAY BE REQUIRED TO ENSURE SUITABILITY OF THESE
DRAWINGS FOR THE SPECIFIC APPLICATION. IT IS THE
USER'S RESPONSIBILITY TO ENSURE INSTALLATION OF THE
EQUIPMENT/SYSTEM IS IN ACCORDANCE WITH
BUILDING/PROJECT SPECIFICATIONS, APPLICABLE CODES AND
STANDARDS.




- NOTES:
1. ALL CONDUIT MAY BE COMBINED ON SAME SUPPORT CHANNEL WHERE PRACTICAL.
 2. SUPPORT CHANNEL LENGTH SHALL NOT BE DETERMINED UNTIL ALL PIPING, CONDUIT, ETC. TO BE SUPPORTED IS COORDINATED.
 3. SUPPORT CHANNEL SPACING SHALL BE NO MORE THAN 10'-0".
 4. UNISTRUT AND CONDUIT INSTALLATION MAY BE REVERSED.

- NOTES:
1. ALL CONDUCTORS IN VERTICAL RACEWAYS SHALL BE SUPPORTED IN ACCORDANCE WITH ARTICLE 300.19 OF NEC. CABLE SUPPORTS SHALL BE LOCATED AT THE INTERVALS REQUIRED BY THE NEC.
 2. CABLE SUPPORT SYSTEM SHALL BE AS MANUFACTURED BY O-Z GEDNEY WITH p0ZI-GRIIP "S-STYLE" WEDGING PLUG OR APPROVED EQUAL.
 3. FOR THREADLESS CONDUIT (RIGID, IMC OR EMT), ATTACH CONDUIT BODY TO MALE THREADS OF A SET SCREW OR COMPRESSION CONNECT, AS PERMITTED BY SPECIFICATIONS.
 4. PROVIDE PULL BOX AT EACH LOCATION OF CABLE SUPPORTS. PULL BOX SHALL BE SIZED AS PER CODE TO ACCOMMODATE ALL CONDUITS.




4 CONDUIT SUPPORT DETAIL
E301.00 N.T.S

2 VERTICAL CABLE SUPPORT DETAIL
E301.00 N.T.S



- NOTES:
1. FOR CONCRETE BLOCK WALLS, CENTER CAULK CP-25 OR PUTTY 303 WITHIN WALL WITH DAMMING ON BOTH SIDES.
 2. RECOMMENDATIONS BASED ON PRODUCT PERFORMANCE PER ASTM E-814 (UL 1479) FIRE TEST AND UL CLASSIFICATION FIRE STOP SYSTEMS 49, 33 AND 91.
 3. WET INSTALLED DEPTH OF CAULK CP-25 OR PUTTY 303 DEPENDS ON TYPE AND SIZE OF PIPE:

PIPE SIZE	WET DEPTH	FIRE RATING
1/2" (13mm)	MAX. 8" (203mm)	2 HRS.
3/4" (19mm)	MAX. 6" (152mm)	3 HRS.
 4. UP TO 40% SHRINKAGE OF CP-25 OR PUTTY 303 IS ACCEPTABLE AFTER WET DEPTH INSTALLATION.
 5. OPTIONS TO MASKING TAPE TO PREVENT SAGGING:
A. INSTALL ADDITIONAL DAMMING MATERIAL OVER PRODUCT TO HOLD WITHIN OPENING.
B. REMOVE PRODUCT FROM CONTAINER AND ALLOW TO AIR CURE IN SMALL BATCHES FOR 12 HRS. THEN HAND FORM INTO OPENING.
 6. WHEN ANNULAR SPACE EXCEEDS 3/4" (19mm), A 28 AWG METAL COVER PLATE MUST BE MECHANICALLY SECURED ATOP THE 3M FIRE BARRIER APPLICATION, OR TIGHTLY PACK NON-COMBUSTIBLE DAMMING MATERIAL ATOP INSTALLED CAULK OR PUTTY.




- NOTES:
1. TYPICAL FOR WOOD AND METAL STUD ROUGH-IN
 2. PLASTER RINGS NOT SHOWN
 3. LOCATE ALL OUTLET BOXES IN ACCORDANCE WITH ARCHITECTURAL AND MECHANICAL DRAWINGS, AND WITH ALL APPLICABLE SHOP DRAWINGS.
 4. IN ACCORDANCE WITH UBC 4304 OUTLETS ON OPPOSITE SIDES OF WALLS OR PARTITIONS IN THE SAME STUD SPACE MUST BE SEPARATED BY A MIN. OF 24" HORIZONTAL DISTANCE.

3 FIRE STOP DETAIL
E301.00 N.T.S

1 DETAIL TYPICAL ROUGH-IN REQUIREMENTS
E301.00 N.T.S

REVISIONS	
Δ ISSUE	DATE



	ELECTRICAL RISER KEYED WORK NOTES:
A.	EXISTING 100 AMPS, 480/277V, 3--PHASE ELECTRICAL PANEL "HPP" SHALL REMAIN. E.C. TO FIELD VERIFY EXACT RATING, SIZE & OPERABLE CONDITION OF EXISTING PANEL "HPP". INFORM ENGINEER FOR ANY DISCREPANCY. COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD. BASE BID ACCORDINGLY.
B.	EXISTING 30 KVA 480/277V TO 208/120V, 3--PHASE STEP DOWN TRANSFORMER FOR THE PROJECT SPACE SHALL REMAIN. E.C. TO FIELD VERIFY EXACT RATING, SIZE & OPERABLE CONDITION OF EXISTING TRANSFORMER. INFORM ENGINEER FOR ANY DISCREPANCY. COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD. BASE BID ACCORDINGLY.
C.	EXISTING 100 AMPS, 120/208V, 3--PHASE ELECTRICAL PANEL "RP-A" SHALL REMAIN. E.C. TO FIELD VERIFY EXACT RATING, SIZE & OPERABLE CONDITION OF EXISTING PANEL "RP-A". INFORM ENGINEER FOR ANY DISCREPANCY. COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD. BASE BID ACCORDINGLY.
D.	NEW 15 KVA 480/277V TO 208/120V, 3--PHASE STEP DOWN TRANSFORMER FOR THE PROJECT SPACE. E.C. TO COORDINATE WITH OWNER/ARCHITECT FOR EXACT LOCATION IN FIELD.
E.	NEW 60 AMPS, 120/208V, 3--PHASE ELECTRICAL PANEL "RP-B" FOR THE PROJECT SPACE. E.C. TO COORDINATE WITH ARCHITECT/OWNER FOR EXACT LOCATION IN FIELD.

RISER GENERAL NOTES:
1. ABOVE RISER DIAGRAM IS FOR REFERENCE PURPOSE ONLY. E.C TO VERIFY EXACT POWER DISTRIBUTION & OPERABLE CONDITION OF EXISTING DEVICES IN FIELD AND INFORM, ENGINEER FOR ANY DISCREPANCY.
2. E.C. SHALL VERIFY THE RATING, SIZE, LOCATION AND OPERABLE CONDITION OF ALL THE EXISTING PANELS AND ELECTRICAL CONNECTION IN FIELD. INFORM ENGINEER FOR ANY DISCREPANCY FOUND BEFORE COMMENCING ANY WORK.
3. E.C. SHALL VERIFY THE INCOMING SERVICE AMPERAGE, VOLTAGE, NUMBER OF PHASES, WIRE SIZE AND DISTRIBUTION IN FIELD.
4. ELECTRICAL CONTRACTOR TO COORDINATE FAULT CURRENT (ISC) RATING WITH UTILITY COMPANY AND AHJ PRIOR TO COMMENCING ANY WORK.

PANEL: HPP (EXISTING)										MOUNTING: RECESSED					
480Y/277		VOLTS,		3	PHASE,		4	WIRE		PANEL LOCATION: EXISTING LOCATION					
MAIN CB:		100A		MLO:	NA		BUS:	EXISTING		MIN,	FED FROM: EXISTING PP-TP1				
NOTE:															
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	MINIMUM BRANCH CIRCUIT	PER PHASE (KVA)			MINIMUM BRANCH CIRCUIT	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.	
						A	B	C							
1	100A/3P	EXISTING PANEL RP-A (VIA 30 KVA TRANSFORMER)	O	7.47	4#3 , 1#8G, 11/4"C	11.91			3#12-3/4"C	4.43	H	AC-1 (EXISTING) ①	20A/3P	2	
3			O	7.47			11.91			4.43	H			4	
5			O	7.47				11.91		4.43	H			6	
7	20A/3P	NEW WATER HEATER (WH-1)	H	3.00	3#10, 1#10G, 3/4"C.	3.00						SPARE	30A/3P	8	
9			H	3.00			3.00							10	
11			H	3.00				3.00						12	
13	30A/3P	SPARE				3.72			3#6 , 1#10G, 3/4"C	3.72	O	NEW PANEL RP-B (VIA 15 KVA TRANSFORMER)	60A/3P	14	
15							3.72			3.72	O			16	
17								3.72		3.72	O			18	
TOTAL LOAD(KVA)						18.63	18.63	18.63							
												TOTAL CONNECTED LOAD		55.88	KVA
												TOTAL DEMAND LOAD		55.88	KVA

PANEL: RP-A (EXISTING)										MOUNTING: EXISTING									
208Y/120 VOLTS, 3 PHASE, 4 WIRE															PANEL LOCATION:		EXISTING LOCATION		
MAIN CB: 100A										MLO: NA		BUS: EXISTING		MIN,		FED FROM: EXISTING CONNECTION			
NOTE:																			
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	MINIMUM BRANCH CIRCUIT	PER PHASE (KVA)			MINIMUM BRANCH CIRCUIT	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.					
						A	B	C											
1	20	UC FRIDGE - 1 DOOR (#5A)	E	0.29	2#12, 1#12G, 3/4"C	2.32			2#10, 1#10G, 3/4"C	2.04	M	GLYCOL PUMP (#011B)	30	2					
3	20A/2P	SOFT SERVE FREEZER (#5B)	E	1.25	2#12, 1#12G, 3/4"C	1.54			2#12, 1#12G, 3/4"C	0.29	E	UNDER COUNTER FRIDGE - 3 DOOR (#7)	20	4					
5			E	1.25				1.25									SPARE	20	6
7		20	LOW TEMP DISHWASHER (#2)	E			1.80	2#12, 1#12G, 3/4"C							1.80				
9	20	SPARE					0.00					SPARE	20	10					
11	20	SPARE						0.00				SPARE	20	12					
13	20A/2P	ICEMAKER & ICE BIN (#1A)	E	1.45	2#12, 1#12G, 3/4"C.	3.53			2#10, 1#10G, 3/4"C.	2.08	E	MM BOILER UNIT (#3B)	30A/2P	14					
15				E		1.45		3.53			2.08			E	16				
17			20	POS (#8)		R	0.72	2#12, 1#12G, 3/4"C						2.80	2.08	E	MM BOILER UNIT (#3B)	30A/2P	18
19	20	EMERGENCY LIGHTS/EXIT LIGHT (EXISTING) 1	L	0.15	EXISTING	2.23			2.08	E	20	20							
21	20	LIGHTING (EXISTING)	L	0.15	EXISTING		0.30		EXISTING	0.15	L	LIGHTING (EXISTING)	20	22					
23	20	LIGHTING (EXISTING)	L	0.15	EXISTING			0.30	EXISTING	0.15	L	LIGHTING (EXISTING)	20	24					
25	20	LIGHTING (EXISTING)	L	0.15	EXISTING	0.30			EXISTING	0.15	L	LIGHTING (EXISTING)	20	26					
27	20	LIGHTING (EXISTING) 1	L	0.15	EXISTING		0.30		EXISTING	0.15	L	LIGHTING (EXISTING)	20	28					
29	20	SPARE						0.15	EXISTING	0.15	L	LIGHTING (EXISTING)	20	30					
31	20	LIGHTING (EXISTING)	L	0.15	EXISTING	0.30			EXISTING	0.15	L	LIGHTING (EXISTING)	20	32					
33	20	CONDENSATE PUMP (EXISTING)	H	1.92	EXISTING		3.84		EXISTING	1.92	H	CONDENSING UNIT (EXISTING)	20	34					
35	20	DRAIN PUMP (DP-2)	M	0.84	2#12, 1#12G, 3/4"C			1.68	2#12, 1#12G, 3/4"C	0.84	M	DRAIN PUMP (DP-1)	20	36					
37	20	SIGNAGE	L	1.00	2#12, 1#12G, 3/4"C	1.00						SPARE	20	38					
39	20	LIGHTING (NEW) LT-1	L	0.15	2#12, 1#12G, 3/4"C		0.15					SPARE	20	40					
41	20	SPARE						0.00				SPARE	20	42					
TOTAL LOAD(KVA)						11.48	9.65	6.18											
										TOTAL CONNECTED LOAD			27.31	KVA					
										TOTAL DEMAND LOAD			22.42	KVA					

PANEL: RP-B (NEW)										MOUNTING: SURFACE						
208Y/120		VOLTS,		3	PHASE,		4	WIRE		PANEL LOCATION:		NEAR TO NEW TRANSFORMER				
MAIN CB:		60A		MLO:		NA		BUS:		125 A		MIN,		FED FROM: NEW TRANSFORMER		
NOTE:																
CKT NO.	TRIP AMPS	DESCRIPTION OF LOAD	LOAD TYPE	LOAD (KVA)	MINIMUM BRANCH CIRCUIT	PER PHASE (KVA)			MINIMUM BRANCH CIRCUIT	LOAD (KVA)	LOAD TYPE	DESCRIPTION OF LOAD	TRIP AMPS	CKT NO.		
						A	B	C								
1	30A/2P	STEAM UNIT (#4B)	E	1.77	2#10, 1#10G, 3/4"C.	3.54			2#10, 1#10G, 3/4"C.	1.77	E	STEAM UNIT (#4B)	30A/2P	2		
3			E	1.77			3.54			1.77	E			4		
5			M	0.10				0.46		0.36	R			6		
7	20	UNDER COUNTER GRAB AND GO FRIDGE (#9)	E	1.44	2#12, 1#12G, 3/4"C.	1.98			2#12, 1#12G, 3/4"C.	0.54	R	GENERAL RECEPTACLE	20	8		
9	20	UNDER COUNTER FRIDGE - 2 DOOR (#6)	E	0.29	2#12, 1#12G, 3/4"C.		0.99		2#12, 1#12G, 3/4"C.	0.70	E	ANGEL JUICER (#21)	20	10		
11	20	COMMERCIAL FOOD BLENDER (#23)	E	1.56	2#12, 1#12G, 3/4"C.			2.91	2#10, 1#10G, 3/4"C.	1.35	E	ELECTRICAL BREWING KETTLE (#22)	30A/2P	12		
13	20	SCALE (#27)	R	0.18	2#12, 1#12G, 3/4"C.	1.53				1.35	E			14		
15	20	CONVEYOR TOASTER (#24)	E	1.60	2#12, 1#12G, 3/4"C.		1.60							SPARE	20	16
17	20	SPARE						0.00				SPARE	20	18		
TOTAL LOAD(KVA)						7.05	6.12	3.37								
										TOTAL CONNECTED LOAD					16.54	KVA
										TOTAL DEMAND LOAD					11.16	KVA

PANEL SCHEDULE KEYED WORK NOTES:

- EXISTING CIRCUIT FOR EXISTING EQUIPMENTS SHALL REMAIN. E.C. TO VERIFY THE CIRCUIT NUMBER, BREAKER RATING, WIRE SIZE & OPERABLE CONDITION OF EXISTING ELECTRICAL CIRCUIT FOR EXISTING EQUIPMENTS IN FIELD. REPLACE IF FOUND INOPERABLE. BASE BID ACCORDINGLY.

PANEL SCHEDULE GENERAL NOTES:

- ALL CIRCUITING SHOWN IS FOR REFERENCE PURPOSE ONLY. E.C. SHALL VERIFY CIRCUITING OF THE EXISTING DEVICES IN FIELD AND INFORM ENGINEER FOR ANY DISCREPANCIES.
- ELECTRICAL CONTRACTOR TO VERIFY THE EXACT PANEL SIZES AND INCOMING FEEDER SIZE.
- ELECTRICAL CONTRACTOR SHALL VERIFY EXACT CIRCUIT NUMBER & BREAKER SIZE OF EXISTING DEVICES IN FIELD.
- E.C. SHALL PROVIDE NEW CIRCUIT BREAKERS IN PLACE OF EXISTING CIRCUIT BREAKERS WHEREVER NECESSARY TO BE IN LINE WITH THE PANEL SCHEDULE.
- E.C. SHALL VERIFY THE EXISTING EQUIPMENT LOAD & RATINGS IN FIELD AND ACCORDINGLY CONSIDER THE ELECTRICAL LOAD IN PANEL BOARD SCHEDULE.



CHA CHA MATCHA
EMPIRE STORES

REVISIONS
Δ ISSUE DATE

PROJECT NUMBER: 22-097

ELECTRICAL RISER
DIAGRAM AND PANEL
SCHEDULE

E401.00

PLUMBING SYMBOLS LIST

-----	DOMESTIC COLD WATER PIPING
---EX.CW---	EXIST. DOMESTIC COLD WATER
-----	DOMESTIC HOT WATER PIPING
---EX.HW---	EXIST. DOMESTIC HOT WATER
-----	HOT WATER RECIRCULATION
-----	VENT PIPING
-----	WASTE (SANITARY SEWER)
-----	INDIRECT WASTE
---EX.SAN---	EXISTING WASTE (SANITARY SEWER)
---EX.V---	EXISTING VENT PIPING
—○	PIPE UP
—◉	PIPE DOWN
⊠	FLOOR DRAIN
⊙	CLEAN OUT
—	WALL CLEAN OUT
—∩—	P-TRAP
⊗	KEY NOTES
⊠	EQUIPMENT NUMBER

PLUMBING ABBREVIATIONS

CO	CLEANOUT
CODP	CLEAN OUT DECK PLATE
CW	COLD WATER
HW	HOT WATER
HWR	HOT WATER RETURN
SAN	SANITARY
V	VENT
W	WASTE
LAV	LAVATORY
WC	WATER CLOSET
TYP.	TYPICAL
DN	DOWN
AFF	ABOVE FINISH FLOOR
FD	FLOOR DRAIN
SQ. FT.	SQUARE FEET
BFP	BACK FLOW PREVENTER
WH	HOT WATER HEATER
EX.	EXISTING

BUILDING DEPARTMENT PLUMBING NOTES:

1. ALL PLUMBING SYSTEMS (SANITARY, WASTE, VENT, WATER, STORM) AND ASSOCIATED EQUIPMENT SHALL BE INSTALLED, OPERATED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF 2014 THE NEW YORK CITY PLUMBING CODE (NYPCP).
2. INSTALLATION OF UNDERGROUND BUILDING SANITARY DRAINAGE AND VENT PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 702.2
3. PROTECTION OF PIPING AND PLUMBING SYSTEM COMPONENTS AS PER SECTION PC 305.
4. TRENCHING, EXCAVATION AND BACKFILL AS PER SECTION PC 306.
5. RODENT PROOFING AS PER PC 304
6. MATERIALS USED IN PLUMBING SYSTEMS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 303, PC 605, PC 702, PC 902.
7. EQUIPMENT CONNECTIONS AND JOINING OF PIPING SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTERS 4, 5, 6, 7, 8 AND 9.
8. DEEP SEAL TRAPS FOR FLOOR DRAINS SHALL BE PROVIDED AS PER PC 1002, AND CLEAN-OUTS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 708
9. BUILDING HOUSE TRAPS SHALL BE PROVIDED AS PER SECTION PC 1002.
10. VERTICAL AND HORIZONTAL PIPING SHALL BE SUPPORTED IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION PC 308
11. WATER SUPPLY SYSTEMS SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 6 SECTION PC 601-603, 604, 606, 607, 608, 610
12. THE SANITARY DRAINAGE SYSTEM SHALL BE SIZED AND INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 7 SECTION PC 701, 704, 705, 706, 707, 708, 711.
13. VENT PIPING FOR THE SANITARY DRAINAGE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF CHAPTER 9 SECTIONS PC 901 THROUGH PC 912 THROUGH PC 917.

PLUMBING DRAWING LIST

P001.00	PLUMBING SYMBOLS, ABBREVIATIONS, NOTES AND SPECIFICATIONS
P002.00	PLUMBING SPECIFICATIONS
P101.00	PLUMBING FLOOR PLANS
P501.00	PLUMBING DETAILS
P601.00	PLUMBING RISER AND SCHEDULES

PROJECT DESCRIPTION

INTERIOR TENANT IMPROVEMENT OF SPACE 1H (832 SF).

SCOPE OF WORK

GENERAL CONSTRUCTION FOR INTERIOR PLUMBING RENOVATION
FOR CHA CHA MATCHA A NEW COMMERCIAL TENANT FIT OUT
OF SPACE 1H, NO CHANGE TO USE.

TANDEM APPLICATIONS

GENERAL CONSTRUCTION [GC] = B00791334-[i1]
PLUMBING [PL] = B00793693-[i1]

PLUMBING SPECIFICATIONS

1. BASIC PLUMBING REQUIREMENTS, MATERIALS AND METHODS
- 1.01 SCOPE
- A. PROVIDE ALL MATERIAL, TOOLS, SUPERVISION AND LABOR INCLUDING ALL MISCELLANEOUS AND INCIDENTAL ITEMS REQUIRED FOR COMPLETE AND OPERABLE PLUMBING INSTALLATIONS AS SHOWN OR DESCRIBED ON THE DRAWINGS AND IN THESE SPECIFICATIONS.
- B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL NEW CONDITIONS AND MATERIALS WITHIN THE CONSTRUCTION AREA. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE OWNER'S SATISFACTION.
- C. OBTAIN ALL PERMITS, PAY ALL PERMIT FEES AND SCHEDULE ALL REQUIRED INSPECTIONS. COPIES OF ALL PERMITS AND INSPECTION CERTIFICATES SHALL BE FORWARDED TO THE OWNER FOR RECORD.
- D. THE GENERAL CONDITIONS OF THE CONTRACT AND ALL DIVISION 1 REQUIREMENTS APPLY TO THE WORK OF THIS SECTION.
- E. THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTING BID TO DETERMINE CONDITIONS AND THE EXTENT OF THE WORK. BY COMMENCING WORK, THE CONTRACTOR ACKNOWLEDGES HIS CONFIRMATION OF ALL CONDITIONS AS ACCEPTABLE WITH REFERENCE TO HIS CONTRACT, SCOPE OF WORK AND BID PRICE SUCH THAT NO ADDITIONAL COMPENSATION SHALL BE FORTHCOMING FOR UNFORESEEN EXISTING CONDITIONS.
- F. IN ALL AREAS SUBJECT TO FREEZING CONDITIONS, THE CONTRACTOR SHALL PROVIDE FREEZE PROTECTION FOR ALL DOMESTIC WATER PIPING INSTALLED UNDER HIS CONTRACT.
- G. ALL ELECTRICAL REQUIREMENTS SHALL BE COORDINATED WITH THE CONTRACTOR FOR ELECTRICAL WORK. THIS CONTRACTOR IS RESPONSIBLE FOR ALL LOW VOLTAGE WIRING FOR EQUIPMENT INSTALLED UNDER HIS CONTRACT. THE CONTRACTOR FOR ELECTRICAL WORK IS RESPONSIBLE FOR LINE VOLTAGE POWER WIRING ONLY.
- H. COLOR AND FINISH SELECTIONS FOR ALL MATERIALS, INCLUDING PAINTING OF PIPING, SHALL BE AS DIRECTED AND/OR APPROVED BY THE ARCHITECT.
- I. MINOR DETAILS NOT SHOWN OR SPECIFIED, BUT NECESSARY FOR THE PROPER AND ACCEPTABLE CONSTRUCTION, INSTALLATION OR OPERATION OF ANY PART OF THE WORK AS DETERMINED BY THE ENGINEER SHALL BE INCLUDED AS IF SPECIFIED OR INDICATED ON THE DRAWINGS.
- J. THIS CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIREMENTS FOR THE INSTALLATION, CONNECTION, EXTENSION OR MODIFICATION TO ALL UTILITY SERVICES WITH RESPECTIVE PROVIDERS INCLUDING PAYMENT OF ALL ASSOCIATED FEES.
- K. THE CONTRACTOR IS RESPONSIBLE FOR ALL PAINTING ASSOCIATED WITH CUTTING AND PATCHING. ALL PAINTING IN AREAS WITH COMPLETE FINISH RENOVATIONS SHALL BE PROVIDED BY THE GENERAL CONTRACTOR.
- 1.02 SUBMITTALS
- A. SUBMITTAL REQUIREMENTS SHALL BE COORDINATED WITH THE ARCHITECT AND AUTHORITIES HAVING JURISDICTION. UNLESS OTHERWISE DIRECTED, CONTRACTOR SHALL PROVIDE SUBMITTALS AS LISTED BELOW.
1. PIPE AND FITTINGS
 2. VALVES
 3. HANGERS AND SUPPORTS
 4. PLUMBING PIPING LAYOUT
 5. TESTS
 6. PLUMBING FIXTURES
 7. WATER HEATERS & ACCESSORIES
 8. DRAIN PUMP
 9. MIXING VALVES
 10. ALL SCHEDULED PLUMBING EQUIPMENT
- B. SUBMITTALS FROM SUPPLIERS OR MANUFACTURERS WHICH DO NOT BEAR THE STAMP OF THE SUBMITTING CONTRACTOR INDICATING THAT THE CONTRACTOR HAS REVIEWED THE SUBMITTAL FOR CONFORMANCE WITH THE PROJECT REQUIREMENTS WILL BE RETURNED REJECTED.
- C. THE ENGINEER'S REVIEW OF SUBMITTALS IS A COURTESY WHICH DOES NOT RELIEVE THE CONTRACTOR FROM CONFORMING WITH CONSTRUCTION DOCUMENTS, REGARDLESS OF THE ACTION INDICATED BY THE SHOP DRAWINGS STAMP.
- D. REVIEW OF SHOP DRAWINGS BY THE ENGINEER SHALL BE LIMITED TO THE INITIAL REVIEW, AND A SECOND REVIEW OF ANY REQUIRED REQUIRED DATA IF THE ENGINEER IS REQUIRED TO REVIEW SHOP DRAWINGS FOR A THIRD (OR MORE) SUBMISSION OF THE SAME ITEM. THE CONTRACTOR SHALL BE LIABLE FOR COMPENSATING THE ENGINEER FOR THESE SUBSEQUENT REVIEWS AS PER THE ENGINEER'S CURRENT HOURLY RATE SCHEDULE.
- E. SUBMIT PROOF OF APPROVAL AND/OR CONFIRMATION OF SATISFACTORY TEST RESULTS TO THE OWNER AND THE ARCHITECT.
- F. SUBMIT TO THE OWNER'S MAINTENANCE PERSONNEL OPERATION AND MAINTENANCE DATA FOR ALL SYSTEM COMPONENTS, SERVICING REQUIREMENTS, INSPECTION DATA, REPLACEMENT PART NUMBERS AND AVAILABILITY AND CONTACT INFORMATION FOR SERVICE/SUPPLY COMPANY.
- G. FOR ALL BELOW GRADE PIPING WHERE ACTUAL INSTALLATION DEVIATES FROM CONSTRUCTION DRAWINGS, THE CONTRACTOR SHALL PROVIDE AS-BUILT DRAWINGS INDICATING BELOW GRADE PIPE LOCATIONS DIMENSIONED TO NEAREST COLUMN LINES.
- H. RECORD AS-BUILT DRAWINGS SHALL BE SUPPLIED TO THE OWNER/TENANT AFTER COMPLETION OF THE WORK SHOWING ANY ALTERATIONS, ADDITIONS AND/OR DELETIONS TO THE SYSTEM(S) INSTALLED.
- 1.03 SUBSTITUTIONS
- A. ALL EQUIPMENT SHALL BE PRODUCTS OF THE SPECIFIED MANUFACTURER OR MANUFACTURERS. ALL BIDS SHALL BE BASED ON THE SPECIFIED MANUFACTURER OR MANUFACTURER'S EQUIPMENT. FOR SUBSTITUTIONS FROM OTHER MANUFACTURER'S EQUIPMENT TO BE CONSIDERED, THE SUBSTITUTION MUST BE INDICATED PRIOR TO BIDDING WITH THE REASON FOR THE PROPOSED SUBSTITUTION IDENTIFIED, AND THE PROPOSED CREDIT TO THE OWNER INDICATED. THE ENGINEER SHALL DETERMINE THE ACCEPTABILITY OF ANY PROPOSED SUBSTITUTIONS.

- B. INSTALL: TO ERECT, MOUNT AND CONNECT, COMPLETE WITH RELATED ACCESSORIES.
- C. PROVIDE: TO FURNISH AND INSTALL.
- D. PLUMBING CONTRACTOR, THE CONTRACTOR, THIS CONTRACTOR: THE CONTRACTOR FOR PLUMBING WORK WHICH IS SPECIFIED HEREIN AND SHOWN ON THESE DRAWINGS.
- E. REFER TO THE NATIONAL STANDARD PLUMBING CODE FOR ADDITIONAL DEFINITIONS.
- 1.05 DRAWINGS

1.05 DRAWINGS

- THE DRAWINGS ARE DIAGRAMMATIC AND ARE INTENDED TO ILLUSTRATE THE GENERAL ARRANGEMENT AND ROUTING OF PIPING AND GENERAL LOCATIONS OF EQUIPMENT. PRECISE LOCATIONS OF EQUIPMENT, RISERS AND STACKS, AND ROUTING AND ELEVATION OF ALL PIPING SYSTEM SHALL BE COORDINATED IN THE FIELD WITH THE ARCHITECT. ARCHITECTURAL DRAWINGS, THE WORK OF OTHER TRADES, EXISTING AND NEW BUILDING CONDITIONS AND/OR THE PREFERENCES OF THE OWNER/TENANT AS CONSTRUCTION PROCEEDS. ALL PIPING SHALL BE INSTALLED CONCEALED IN FINISHED SPACES, UNLESS NOTED OTHERWISE.
- B. PROVIDE ALL NECESSARY INCIDENTAL MATERIALS AND ACCESSORIES REQUIRED TO MAKE THE WORK COMPLETE IN ALL RESPECTS, EVEN IF NOT PARTICULARLY SHOWN OR SPECIFIED.
- C. REFER TO PLUMBING EQUIPMENT/FIXTURE SCHEDULE ON THE DRAWINGS FOR ALL FIXTURE AND EQUIPMENT SPECIFICATIONS.
- D. REFER TO FIXTURE CONNECTION SIZE SCHEDULE FOR ALL FIXTURE ROUGHING SIZE REQUIREMENTS.
- E. VERIFY ALL INDICATED CONDITIONS BEFORE STARTING WORK AND REPORT ANY DISCREPANCIES. THE DRAWINGS REFLECT CONDITIONS WHICH CAN BE REASONABLY INTERPRETED FROM THE EXISTING VISIBLE CONDITIONS OR FROM DRAWINGS AND INFORMATION FURNISHED BY THE OWNER.
- F. LOCATE ALL FIXTURES AND EQUIPMENT AS PER THE FINAL ARCHITECTURAL DRAWINGS.

1.06 PRODUCTS

- A. SANITARY AND VENT PIPING:
1. ABOVE GRADE PIPING SHALL BE HUBLESS CAST IRON PIPE WITH STAINLESS STEEL COUPLINGS AND ELASTOMERIC GASKETS WITH A MINIMUM NO. OF BANDS PER COUPLING AS PER CISPI 310-12.
 2. SLOPE OF DRAINAGE SYSTEM SHALL BE 1/8" PER FOOT OF RUN FOR PIPE OVER 3" (I.D.) AND 1/4" PER FOOT OF RUN FOR PIPE 3" AND SMALLER (I.D.). VENT PIPING SHALL BE PITCHED TO DRAIN.
 3. ALL CAST IRON SOIL PIPE AND FITTINGS SHALL BE MARKED WITH THE COLLECTIVE TRADEMARK OF THE CAST IRON SOIL PIPE INSTITUTE (CISPI) AND BE LISTED BY NSF INTERNATIONAL.
- B. DOMESTIC WATER PIPING:
1. ABOVE GRADE WATER PIPING SHALL BE TYPE "L" HARD-DRAWN COPPER TUBE.
 2. FITTINGS IN DOMESTIC WATER PIPING SHALL BE WROUGHT COPPER OR CAST BRASS.
 3. JOINTS SHALL BE MADE WITH LEAD-FREE SOLDER.
 4. THE ENTIRE DOMESTIC WATER DISTRIBUTION SYSTEM SHALL BE INSULATED INCLUDING ALL VALVES, FITTINGS, ETC.
 5. COMPLY WITH NSF 61 FOR MATERIALS FOR WATER-SERVICE PIPING AND SPECIALTIES FOR DOMESTIC WATER.

6. ALL DOMESTIC WATER PIPING ABOVE GRADE SHALL BE FIRE-RETARDANT, FACTORY-APPLIED JACKET. PROVIDE COLD WATER PIPING WITH FACTORY-APPLIED VAPOR BARRIER. INSULATION REQUIREMENT SHOULD COMPLY 2020 NYC ENERGY CONSERVATION CODE SECTION C404.4 WITH BELOW TABLE.

MINIMUM PIPE INSULATION THICKNESS							
FLUID OPERATING TEMPERATURE RANGE AND USAGE (°F)	INSULATION CONDUCTIVITY		NOMINAL PIPE OR TUBE SIZE (INCHES)				
	CONDUCTIVITY BTU IN. / (H. FT ² °F)	MEAN RATING TEMPERATURE, °F	<1	1 to < 1½	1½ to < 4	4 to < 8	≥8
141–200	0.25–0.29	125	1.5	1.5	2.0	2.0	2.0
105–140	0.21–0.28	100	1.0	1.0	1.5	1.5	1.5
40–60	0.21–0.27	75	0.5	0.5	1.0	1.0	1.0

7. WATER DISTRIBUTION SYSTEM AS PER NYC ENERGY CONSERVATION CODE 2020 C404.7, HAVING ONE OR MORE RECIRCULATION PUMPS THAT PUMP WATER FROM A HEATED-WATER SUPPLY PIPE BACK TO THE HEATED-WATER SOURCE THROUGH A COLD-WATER SUPPLY PIPE SHALL BE A DEMAND RECIRCULATION WATER SYSTEM. PUMPS SHALL HAVE CONTROLS THAT COMPLY WITH BOTH OF THE FOLLOWING:
 - a. THE CONTROL SHALL START THE PUMP UPON RECEIVING A SIGNAL FROM THE ACTION OF A USER OF A FIXTURE OR APPLIANCE, SENSING THE PRESENCE OF A USER OF A FIXTURE OR SENSING THE FLOW OF HOT OR TEMPERED WATER TO A FIXTURE FITTING OR APPLIANCE.
 - b. THE CONTROL SHALL LIMIT THE TEMPERATURE OF THE WATER ENTERING THE COLD-WATER PIPING TO 104°F (40°C).
8. AS PER NYC ENERGY CONSERVATION CODE 2020 C404.6.1, HEATED-WATER CIRCULATION SYSTEMS SHALL BE PROVIDED WITH A CIRCULATION PUMP. THE SYSTEM RETURN PIPE SHALL BE A DEDICATED RETURN PIPE OR A COLD WATER SUPPLY PIPE. CONTROLS FOR CIRCULATING HOT WATER SYSTEM PUMPS SHALL START THE PUMP BASED ON A SENSITIZED IDENTIFICATION OF HOT WATER WITHIN THE OCCUPANCY. THE CONTROLS SHALL AUTOMATICALLY TURN OFF THE PUMP WHEN THE WATER IN THE CIRCULATION LOOP IS AT THE DESIRED TEMPERATURE AND WHEN THERE IS NO DEMAND FOR HOT WATER.
9. HEATED WATER SUPPLY PIPING SHALL BE IN ACCORDANCE WITH NYC ENERGY CONSERVATION CODE 2020 SECTION C404.5.1. THE HW PIPE LENGTH FROM THE NEAREST SOURCE OF HEATED WATER TO THE TERMINATION OF THE FIXTURE SUPPLY PIPE SHALL BE AS PER FOLLOWING TABLE.

NOMINAL PIPE SIZE (INCHES)	MAXIMUM PIPING LENGTH (FEET)	
	PUBLIC LAV	OTHER FIXTURES
¾"	3'	50'
½"	2'	43'
¾"	0.5'	21'
1"	0.5'	13'
1½"	0.5'	8'
1 1/2"	0.5'	6'
2" OR LARGER	0.5'	4'

10. SEAL ALL JOINTS BETWEEN SEGMENTS OF INSULATION.

11. PROVIDE SHIELDS BETWEEN HANGERS AND INSULATION.

- ### C. PRESS JOINERY SYSTEM:

- a. **FITTINGS** $\frac{1}{2}$ " – 4":

1. WHERE APPROVED BY THE LOCAL JURISDICTION, THE NIBCO PRESS SYSTEM MAY BE USED AT THE CONTRACTOR'S OPTION FOR THE FOLLOWING BUILDING SERVICES PIPING -20°F TO +250°F UP TO 200 PSI:
 - HOT AND COLD DOMESTIC WATER; FITTINGS AND VALVES SHALL BE NSF-61 APPROVED.
 - POTABLE WATER; FITTINGS AND VALVES SHALL BE NSF-61 APPROVED.
 - HOT WATER HEATING SERVICE

ALL LEAD FREE WROT COPPER PRESS FITTINGS SHALL BE MADE FROM COMMERCIALLY PURE COPPER MILL PRODUCTS PER ASTM B 75 ALLOY C12200. THESE FITTINGS SHALL BE THIRD-PARTY CERTIFIED TO NSF/ANSI 61 ANNEX G AND COMPLY WITH NEW YORK CITY HEALTH AND SAFETY CODE NYC PC 2014 AND VERMONT ACT 193. NIBCO LEAD FREE CAST DEZINCIFICATION-RESISTANT (DZR) FITTINGS SHALL BE MADE FROM A HIGH QUALITY LEAD FREE PERFORMANCE BRONZE ALLOY PER ASTM B 584 ALLOY C63000. ALL FITTINGS SHALL BE COMPATIBLE WITH SEAMLESS K, L OR M COPPER TUBE MADE TO ASTM B 88. FITTINGS SHALL HAVE A MAXIMUM NON-SHOCK WORKING PRESSURE OF 200 PSI BETWEEN THE TEMPERATURES OF -20°F AND +250°F. ELASTOMERIC SEALS WITH LEAK DETECTION DESIGN SHALL BE MADE OF EPDM MATERIAL, AND THE FITTINGS SHALL BE MANUFACTURED WITH AN INBOARD BORE DESIGN. NIBCO PRESS FITTINGS MEET ALL PERFORMANCE REQUIREMENTS OF ASME B16.22 AND ALL FITTINGS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS AND ACCORDING TO LOCAL PLUMBING AND MECHANICAL CODES. THE PRESS TO-CONNECT JOINT SHALL BE MADE WITH PRESSING TOOLS AND JAW SETS RECOMMENDED AND AUTHORIZED BY NIBCO. ALL FITTINGS, VALVES AND TOOLS SHALL BE PROVIDED BY SAME MANUFACTURER; NIBCO.

- b. VALVES 2" AND SMALLER: BALL VALVES: (ON/OFF, ISOLATION OR THROTTLING)
1. BALL VALVES (STAINLESS STEEL BALL AND STEM) WITH MALE OR FEMALE PRESS-TO-CONNECT ENDS SHALL BE RATED AT 200 PSI CWP +250°F MAXIMUM. NIBCO LEAD FREE VALVES SHALL BE MANUFACTURED IN ACCORDANCE WITH ASTM F1110. ALL VALVES SHALL BE CONSTRUCTED OF DEZINCIFICATION-RESISTANT (DZR) BRONZE BODIES AND END PIECES AND SHALL BE MADE FROM A HIGH QUALITY LEAD FREE PERFORMANCE BRONZE ALLOY PER ASTM B 584 ALLOY C87850. NO BRASS CONTAINING MORE THAN 15% ZINC SHALL BE APPROVED. VALVE SHALL HAVE REINFORCED TEFLON BALLS. LOW-CURVE PROJECT STEM. SOLID STAINLESS STEEL BALL AND STEM. NO HOLLOW CHROME PLATED BALLS ACCEPTED. ALL VALVES SHALL BE FULL PORT. ALL ELASTOMERIC SEALS SHALL HAVE LEAK DETECTION DESIGN.
- WHERE PIPING IS TO BE INSULATED, BALL VALVES SHALL BE EQUIPPED WITH 2" EXTENDED HANDLES OF NON-THERMAL CONDUCTIVE MATERIAL. HANDLE TO HAVE EXTENDED SLEEVE INCORPORATING AN INSULATION PLUG TO PROVIDE A VAPOR BARRIER AND ALLOW VALVE OPERATION WITHOUT DISTURBING THE INSULATION, AND A MEMORY STOP, WHICH CAN BE SET AFTER INSTALLATION.
- ACCEPTABLE VALVES: (NSF-61, NON-INSULATED LINES): NIBCO
PC585-66-FL, -HC, -UL
- ACCEPTABLE VALVES: (NSF-61, INSULATED LINES): NIBCO
PC585-66-FL-NS, -HC, -UL

1. VALVES WITH PRESS-TO-CONNECT ENDS SHALL BE RATED TO 200 PSI CWP AT +250°F MAXIMUM. NIBCO LEAD FREE VALVES SHALL BE MANUFACTURED IN ACCORDANCE WITH MSS SP-80 AND CONSTRUCTED OF DEZINICIFICATION-RESISTANT (DZR) BRONZE BODY & CAP SHALL BE MADE FROM A HIGH QUALITY LEAD FREE PERFORMANCE BRONZE ALLOY PER ASTM B 584 ALLOY C87850. DISK SHALL BE TITANIUM. ALL ELASTOMERIC SEALS SHALL HAVE LEAK DETECTION DESIGN.
- ACCEPTABLE CHECK VALVES: NIBCO PS413-Y-LF; Y PATTERN, SWING TYPE CHECK VALVE; NIBCO PS480-Y-LF : IN-LINE SPRING LOADED SILENT CHECK VALVE

- d. BUTTERFLY VALVES 2-1/2" - 4", (ON/OFF, ISOLATION OR THROTTLING)

1. BUTTERFLY VALVES WITH FEMALE LEAD FREE PRESS-TO-CONNECT ENDS SHALL BE RATED AT 200 PSI. CWP TO +250°F MAXIMUM. VALVES SHALL BE MANUFACTURED IN ACCORDANCE WITH MSS SP-67 AND CONSTRUCTED OF A DUCTILE-IRON BODY, FOR SUBSTITUTION OF THE RIGHT SHOWN. THE VALVE SHALL HAVE A DISC AND LINING SUITABLE FOR POTABLE WATER, VALVES SHALL BE SUITABLE FOR BI-DIRECTIONAL DEAD END SERVICE AT FULL RATED PRESSURE, ONE-PIECE TYPE 414 STAINLESS-STEEL STEM, COPPER BUSHING, FASTENERS AND RINGS SHALL NOT BE USED TO ATTACH TO SUBSTITUTION. DISC AND LINING SHALL BE OF THE FOLLOWING: ALUMINUM-BRONZE DISC, AND MOLDED-IN EPDM SEAT (LINER). ALL ELASTOMERIC SEALS SHALL HAVE LEAK DETECTION DESIGN.

- ACCEPTABLE VALVES: NIBCO PFD2000 SERIES (NSF-61)
- GD4765N-LF (NSF-61)

- D. ELECTRIC WATER HEATER(WH-1)

1. TANKS SHALL 40 GALLON CAPACITY AND SHALL HAVE 150 PSI WORKING PRESSURE AND BE EQUIPPED WITH EXTRUDED HIGH DENSITY ANODE.
2. NON-CFC FOAM INSULATION COVERS THE SIDES AND TOP OF THE TANK, REDUCING HEAT LOSS.

3. ELECTRIC HEATING ELEMENTS SHALL BE LOW WATT DENSITY.

La Cha
MATCHA

CHA CHA MATCHA
EMPIRE STORES


REVISIONS

[illegible]


PROJECT NUMBER: 22-097

PLUMBING SYMBOLS, ABBREVIATIONS, NOTES AND SPECIFICATIONS

P001.00



WATER FLOOR PLAN | 2
1/4" = 1'-0"



SANITARY FLOOR PLAN | 1
1/4" = 1'-0"

WATER KEY NOTES

- REPLACE THE EXISTING TANKLESS WATER HEATER WITH NEW STORAGE WATER HEATER AS PER PLUMBING SCHEDULE. HOT WATER PIPING REMAINS SAME. HOT WATER RETURN PIPE NEED TO BE PROVIDED. CONTRACTOR TO CONFIRM THE LOCATION AND SPACE AVAILABILITY WITH ARCHITECT OR CLIENT.
- CONNECT NEW 1" WATER SUPPLY LINE TO EXISTING 1" WATER SUPPLY LINE. CONTRACTOR TO FIELD VERIFY THE EXACT LOCATION AND SIZE ON SITE.
- CONNECT NEW MOP SINK FAUCET TO EXISTING CW & HW PIPING FROM EXISTING MOP SINK WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW DISHWASHER TO EXISTING HW PIPING FROM EXISTING DISHWASHER WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW HAND SINK FAUCET TO EXISTING CW & HW PIPING FROM EXISTING SINK WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW FREEZER TO EXISTING CW PIPING FROM EXISTING HOT WATER DISPENSER WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW STEAMER UNIT TO EXISTING CW PIPING FROM EXISTING ICE MAKER WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW STEAM UNIT TO EXISTING CW MAIN PIPING WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW STEAMER UNIT TO EXISTING CW PIPING FROM EXISTING EXPRESSO WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- CONNECT NEW STEAM UNIT TO EXISTING CW PIPING FROM EXISTING RINSER WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.
- REPLACE THE EXISTING 3/4" COLD WATER PIPING WITH NEW 1" COLD WATER PIPING WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE LOCATION AND SIZE OF EXISTING PIPING.
- PLACE THE NEW EXPANSION TANK AS PER THE SCHEDULE ON THE EXISTING 3/4" COLD WATER PIPING. CONTRACTOR TO FIELD VERIFY THE REQUIREMENT OF EXPANSION TANK.
- PLACE THE NEW HOT WATER CIRCULATION PUMP AS PER THE SCHEDULE ON THE NEW 3/4" HWR PIPING. CONTRACTOR TO FIELD VERIFY THE REQUIREMENT OF HOT WATER CIRCULATION PUMP.
- NEW HWR PIPING TO BE CONNECTED TO THE EXISTING HW PIPING FOR THE RINSE SINK WITH BALANCING VALVE.
- CONNECT NEW GLASS RINSER TO EXISTING CW MAIN PIPING WITH ASSOCIATED ACCESSORIES AND FITTINGS. CONTRACTOR TO FIELD VERIFY THE CONDITION OF EXISTING PIPING AND REPLACE IF REQUIRED.

SANITARY KEY NOTES

- EXISTING TENANT TRAY STYLE SLUMP PUMP WILL BE REPLACED WITH NEW DRAIN PUMP (DP-1) INSTALLED BELOW MOP SINK.
- CONNECT NEW 2" SANITARY PIPE TO EXISTING SANITARY PIPE IN CEILING. CONTRACTOR TO FIELD VERIFY THE EXACT LOCATION AND SIZE OF THE SANITARY PIPE. UPGRADE THE EXISTING SANITARY PIPE IF REQUIRED.
- CONNECT NEW 2" VENT PIPE TO EXISTING VENT PIPE IN CEILING. CONTRACTOR TO FIELD VERIFY THE EXACT LOCATION AND SIZE OF THE VENT PIPE. UPGRADE THE EXISTING VENT PIPE IF REQUIRED.
- ROUTE 3/4" INDIRECT WASTE PIPE FROM ICE MAKER & ICE BIN IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 1" INDIRECT WASTE PIPE FROM DISHWASHER IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 2" INDIRECT WASTE PIPE FROM STEAMER UNIT IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 2" INDIRECT WASTE PIPE FROM MOP SINK IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 2" INDIRECT WASTE PIPE FROM STEAM UNIT IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 1" INDIRECT WASTE PIPE FROM ICE BIN IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 1/2" INDIRECT WASTE PIPE FROM GLASS RINSER IN TO THE CHACHA DRIP TRAY WITH APPROVED AIR GAP.
- ROUTE 1 1/2" INDIRECT WASTE PIPE FROM GRAB-N-GO FRIDGE IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 2" INDIRECT WASTE PIPE FROM CHA CHA MATCHA DRIP TRAY IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- ROUTE 1/2" INDIRECT WASTE PIPE FROM HAND SINK IN TO THE FUNNEL DRAIN WITH APPROVED AIR GAP.
- EXISTING FLOOR DRAIN TO REMAIN WITH EXISTING PLUMBING CONNECTIONS.




CHA CHA MATCHA
EMPIRE STORES

REVISIONS	
Δ ISSUE	DATE

PROJECT NUMBER: 22-097

PLUMBING FLOOR
PLANS

P101.00




CHA CHA MATCHA
EMPIRE STORES

REVISIONS	
Δ ISSUE	DATE

PROJECT NUMBER: 22-097

PLUMBING
DETAILS


P501.00



SANITARY RISER DIAGRAM

NTS

REFER SANITARY KEY NOTES ON SHEET P101.00



WATER SUPPLY RISER DIAGRAM

NTS

REFER WATER KEY NOTES ON SHEET P101.00

TAG	QTY	EQUIPMENT	MANUFACTURER/PRODUCT NO.	DIMENSIONS	WATER		WASTE		REMARKS
					COLD	HOT	DIRECT	INDIRECT	
1A	1	ICE MAKER	ICE-O-MATIC MODEL NO. CIM1136HA	30.25"L X 24.25"W X 26.9"H	3/8"	—	—	3/4"	2 GPM, 45 PSI
1B	1	ICE BIN	B110PS ICE BIN	48"L X 31"W X 50"H	—	—	—	3/4"	
2	1	LOW TEMP DISHWASHER	ECOLAB/E-ULT	26.5"L X 24"W X 34"H	—	5/8"	—	1"	15-25 PSI 140°F
3B	2	STEAMER UNIT	MAYAM/CUSTOM	20"L X 21"W X 25"H	3/8"	—	—	2"	2 GPM, 45 PSI
4B	2	STEAM UNIT	MAYAM/CUSTOM	15"L X 21"W X 15"H	3/8"	—	—	2"	2 GPM, 45 PSI
5B	1	SOFT SERVE FREEZER	TAYLOR/C161	23"L X 26"W X 29"H	1/2"	—	—	—	COLD WATER CONNECTION WITH HOSE BIB
9	1	UNDERCOUNTER GRAB AND GO FRIDGE	OASIS/CO33R	36-1/4" L X 32-3/8"D X 33-3/4"H	—	—	—	1-1/2"	
11A	1	CUSTOM CHACHA DRIP TRAY	CUSTOM	20"L X 10"W	—	—	—	2"	
11D	2	CUSTOM CHACHA DRIP TRAY	CUSTOM	30"L X 10"W	—	—	—	2"	
12	1	DROP-IN ICE BIN	ADVANCE TABCO/D-30-IBL-7	27"L X 18"W X 14"H	—	—	—	1"	
14	1	MOP SINK	TO BE DECIDED	TO BE DECIDED	—	—	—	2"	
16	1	HAND SINK	REGENCY/600UMB1520	16.5"L X 12.5"W X 10"H	—	—	—	1-1/2"	
17	1	HAND SINK FAUCET	VOLA/RV1 WHITE	8"L X 1.5"W X 9"H	1/2"	1/2"	—	—	
18	1	MOP SINK FAUCET	WATERLOO/750FMSB	8"L X 9"W X 14.5"H	1/2"	1/2"	—	—	15-20 PSI 110°F
26	2	GLASS RINSER	MICRO MATIC USA/MM-5821	6.5"L X 6.5"W X 3/4"H	1/2"	—	—	1/2"	BSP THREAD WATER INLET PIPE

HOT WATER HEATER											
TAG No.	NO. OF ELEMENTS	FIXTURES SERVING	STORAGE GALONS	RECOVERY CAP. (GPH @ RISE)	TYPE	ELECTRICAL				MANUFACTURER & MODEL NO.	REMARKS
						VOLTS	PHASE	HERTZ	INPUT KW		
WH-1	2	DISHWASHER, HAND SINK AND MOP SINK	40	36 GPH @ 100°F	ELECTRIC WATER HEATER	480	3	60	9	BRADFORD WHITE LE340S3-3	-DIMENSIONS 22"DIA X 47-3/16"H -HEATERS SHALL HAVE 150 PSI WORKING PRESSURE.

RECIRCULATING PUMP SCHEDULE						
MARK	SERVICE	QTY	GPM	TOTAL HEAD FT.	MOTOR HP	MANUFACTURER & REMARKS
HWCP-1	HW RECIRCULATION	1	2	10	0.115	GRUNDFOS UPS 15-18 BUCS W/AQUASTAT & TIMER

DRAIN PUMP SCHEDULE										
MARK	MANUFACTURER	MODEL	GPM	TOTAL HEAD FT.	VOLTAGE	PHASE	HP	AMPS	LOCATION	NOTES
<u>DP-1</u>	LIBERTY PUMPS	405-SERIES	20	20	115	1	1/2	7.3A	BELOW MOP SINK	DIMENSIONS - 14.75"(D) & 14.1"(H) CONTROLLED WITH A PIGGY BACK STYLE ON/OFF FLOAT SWITCH. MAX. LIQUID TEMPERATURE - 180°F
<u>DP-2</u>	LIBERTY PUMPS	405-SERIES	32	20	115	1	1/2	7.3A	BELOW HAND SINK	DIMENSIONS - 14.75"(D) & 14.1"(H) CONTROLLED WITH A PIGGY BACK STYLE ON/OFF FLOAT SWITCH. MAX. LIQUID TEMPERATURE - 70°F

EXPANSION TANK SCHEDULE				
ITEM	SERVICE	GALLONS	MAKE	REMARKS
EXPANSION TANK (ET-1)	HOT WATER	2	AMTROL ST-5	DIMENSIONS- 13"(h)x8"(dia.) SHIPPING WEIGHT- 5 LBS

THERMOSTATIC MIXING VALVE SCHEDULE										
ITEM	LOCATION	SERVING	SERVICE	PIPE SIZE (INCHES)	CAPACITY RANGE (GPM)		TEMP. RANGE (°F)		MANUFACTURER & MODEL NO.	REMARKS
					MIN.	MAX.	MIN.	MAX.		
MIXING VALVE	NEAR WATER HEATER	DISHWASHER, HAND SINK AND RINSE SINK	HOT WATER	3/4	0.1	45	100	160	ACORN MODEL MV17-2	-BRASS BODY -ASSE 1017 LISTED -CSA APPROVED

[illegible]